



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

ANNEXURE- A

Page: 01 of 03

Material :PROCUREMENT OF 1600 M. TON OF LIME STONE POWDER.

Due Date:

Tender Enquiry No: LE/PT/WS/LS/17002/17

Bid Bond Value : PKR:196,000/-

EVALUATION WILL BE CARRIED OUT ON ITEM WISE

Attachment(if any) : YES

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	LIMESTONE POWDER (CALCIUM CARBONATE)	1200		Metric Ton					
2	LIMESTONE POWDER (CALCIUM CARBONATE)	400		Metric Ton					

Special Note:- The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- (1) DELIVERY PERIOD: AS PER SHEDULE ATTACHED. (2) DELIVERY LOCATIONS: ITEM # 1 AT KHADEJI BASE STORE & ITEM # 2 AT CHAK NURANG OIL FIELD. (3) PAYMENT: "100% AFTER DELIVERY" (4) BID VALIDITY: 120 DAYS FROM DATE OF TECHNICAL BI OPENING.

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.

TECHNICAL SPECIFICATIONS SHEET
OF
LIME STONE POWDER (CALCIUM CARBONATE)

A) TECHNICAL SPECIFICATIONS

SR. NO.	PHYSICAL PROPERTIES	REQUIRED SPECIFICATIONS	EXACT VALUE OF THE OFFERED PRODUCT
01.	APPEARANCE	FREE FROM DIRT AND FOREIGN MATTER	
02.	SPECIFIC GRAVITY (S.G)	2.65 (MINIMUM)	
03.	PERCENTAGE PURITY AS CaCO ₃	95% (MINIMUM)	
04.	SOLUBILITY IN 15% HCl	95% (MINIMUM)	
05.	WATER SOLUBLE CONTENTS	LESS THAN 200 PPM	
06.	RETENSION ON 200 US MESH SIEVE	LESS THAN 05% BY WEIGHT	

B) PACKAGING:

The Lime stone powder should be packed as 01 M.Ton export quality brand new jumbo bags having inner polythene liner (Transparent and having minimum weight of 800 grams / liner) for rendering the material completely moisture proof. The packaging of the required mud chemical should be of international standards and capable to safe transportation during road journey from manufacturing facility to OGDCL stores & well sites and to withstand prolonged weather conditions at the storage points and at the well sites / locations.

C) INSTRUCTIONS TO THE BIDDERS/ TERMS & CONDITIONS:

1. The quantities of indented material are tentative & can be increased/ decreased according to the requirement.
2. **Delivery period** of the whole consignment will be **180 Days**, _____ after the issuance of LPO from OGDCL, the supplier will have to provide the indented quantities, as follows, failing to which action will be taken as per rules.

FOR KDS = 03 equal consignment within 60 Days successively.

FOR CNG = 02 equal consignment within 90 Days successively.

3. **Minimum Shelf life** of the quoted product should not be less than **03 years**.
4. Technical specifications sheet of the quoted product duly filled in must be enclosed with the technical bid.
5. The bidder must have to provide the **1.0 Kg** sample of the quoted product and sample of the packing bag along with the technical bid. Without the submission of the product & packaging sample bid will not be entertained.
6. All submitted bids will be evaluated strictly on the basis of TOR of this particular Tender Enquiry as well as previous performance (supply record) of bidder, failing which will lead to disqualification of Bid thereof.
7. Prior to the supply of the material, the supplier will be responsible for carrying out the inspection of the material if desired by the indenting department.
8. Material will be accepted after the physical inspection & lab evaluation report of the representative sample drawn by the inspection committee from the material delivered at required locations.
9. On receipt of the material, if it is found substandard after testing / use, then the supplier shall have to lift the entire rejected consignment and replace the substandard material with the material conforming to the tender specifications at his own cost within one month.