



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

ANNEXURE - A

Page: 01 of 02

Material : **EXPLOSION PROOF MOTORS**

Due Date:

Tender Enquiry No: **LE/PT/P&P/17010-A/17**

Bid Bond Value : **PKR:75,000/-**

EVALUATION WILL BE CARRIED OUT ON FULL

Attachment(if any) : **YES**

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	EXPLOSION PROOF ELECTRIC MOTOR,RATING MCR,30 KW, 415 V, 3 PHASE, 50 HZ,FULL LOAD CURRENT 51.5 AMP,RPM 1460. (FOR DETAIL SEE ATTACHMENT)	2		Number					

Special Note:- The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- (1) DELIVERY LOCATION: SINJHORO GAS PLANT (SANGHARR). (2) DELIVERY PERIOD: WITHIN 120 DAYS AFTER LPO ISSUANCE
- (3) PAYMENT: "100% AFTER DELIVERY" (4) PRICE VALIDITY: 120 DAYS AFTER BID OPENING.

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.

GENERAL SPECIFICATIONS FOR INDENT SGF/ELECT/2017/065

Page 2

EXPLOSION PROOF MOTORS
 INSULATION CLASS F , POLES 04 , STARTING MODE DOL , DESIGN CLASS B TYPE
 TIL FORM FBKW , FRAME SIZE 200 DL
 ENCLUSURE TYPE TFFC Ex'n'
 IP RATING IP 54 , HAZARDOUS CERT NO. 960
 CONNECTION DELTA
 CLASS I ZONE II CT 3 MOTOR HEATERS (ANTI CONDENSATE) 52 WATTS
 MAIN CABLE BOX TO SUIT 25 MM2
 JUNCTION BOXES IP65
 AMBIENT TEMP 50 DEGREES CELCIUS
 BEARING D.E. 6312 N.D.E. 6312
 01 MOTOR IS FLANG TYPE
 OTHER 01 MOTOR IS FOOT MOUNTED

Page: 02 of 02

TERMS & CONDITIONS FOR INDENT SGF/ELECT/2017/065

- 1) OEM TO CONFIRM THAT SUPPLIED MOTOR IS BRAND NEW WITH STANDARD WARANTEE/GUARANTEE.
- 2) OEM TO SUPPLY THE MOTOR IN STANDARD PACKING.