



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Material : **FABRICATION & SUPPLY OF MUD TANKS**

Tender Enquiry No: **PROC/LF/DRG-17147/17**

EVALUATION WILL BE CARRIED OUT ON FULL

Due Date:

Bid Bond Value : RS. 1,050,000/-

Attachment(if any) : YES

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	TANK SHAKER 35 FT. X 10 FT. X 8 FT. HIGH COMPLETE WITH 4 FT. EXTENSION TO ACCOMODATE D-SANDER PUMP (INCLUDING ACCESSORIES,INTER CONNECTIONS & FLANGES ETC.) AND COMPLETE WITH OTHER FITTINGS. P# ASY TANKS.	2		Number					
2	TANK INTERMEDIATE 35 FT. X 10 FT. X 8 FT. HIGH COMPLETE WITH 4 FT. EXTENSION TO ACCOMODATE D-SILTER PUMP (INCLUDING ACCESSORIES,INTER CONNECTIONS & FLANGES ETC.) AND WITH OTHER FITTINGS. P# ASY TANKS.	2		Number					
3	TANK SUCTION 35 FT. X 10 FT. X 8 FT. (INCLUDING ACCESSORIES,INTER CONNECTIONS & FLANGES ETC.) HIGH COMPLETE WITH FITTINGS. P# ASY TANKS.	2		Number					
4	TANK RESERVE 35 FT. X 10 FT. X 8 FT. (INCLUDING ACCESSORIES,INTER CONNECTIONS & FLANGES ETC.) HIGH COMPLETE WITH FITTINGS.(WITH PARTITION) P# ASY TANKS.	2		Number					
5	TANK RESERVE 35 FT. X 10 FT. X 8 FT. (INCLUDING ACCESSORIES,INTER CONNECTIONS & FLANGES ETC.) HIGH COMPLETE WITH FITTINGS.(WITHOUT PARTITION) P# ASY TANKS.	2		Number					

Special Note:- The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- DELIVERY TERM:F.O.R BASE STORE ISLAMABAD WITHIN 6 MONTHS AFTER ISSUANCE OF LPO, PAYMENT TERM: AFTER DELIVERY,

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.

TERMS & CONDITIONS FOR BIDDERS.

INDENT No. M (RMP)/L-FAB/22 for Fabrication of 02 Sets (10 units) of Skid Mounted Mud Tanks for Rig N-2 & N-55.

1. All the bidders are required to submit, their sale record for the last 05 years to confirm manufacturing and supply of mud tanks to drilling companies. In case of purchasers other than OGDCL, their e-mail address, fax no. and phone number must be provided.
2. The new mud tanks are required to replace the existing ones complete with stairs (for access from ground to tanks surface), walk ways with safety hand rails and toe boards, standard arrangement for bottom lifting, surface grating (stairs tread type), arrangement for interconnection, mechanism for connection of mud pumps suction, arrangement for cleaning, top protection against rain water, provision of foundations for allied equipment installations, provision of cable trays etc.
3. Bidders/ Manufacturers may visit OGDCL Rig N-2 and Rig N-55 at their own expense to observe already installed skid mounted mud tanks and allied accessories for having complete information of each part regarding design, size, dimensions, specifications and other accessories like various types of valves, holes, flow lines, gun lines, water lines, flanges, manifolds etc. which may be helpful in preparation of detailed working drawings.
4. Bidders are required to submit detailed working drawings along with technical bid for OGDCL technical evaluation/ approval.
5. Tanks to be fabricated and supplied as per OGDCL approved drawings.
6. OGDCL, as per its own requirement, will have the right to suggest minor changes (if required) in drawings of the qualified bidder. Such changes to be duly approved by OGDCL.
7. A team of OGDCL shall pay four visits at manufacturing site/work shop of the qualified bidder as follows.
 - Stage-1: To inspect the material of tank structures prior starting fabrication activity.
 - Stage-2: To inspect the fabricated base structures of mud tanks.
 - Stage-3: To inspect the completed mud tank structures & Hydrostatic Test procedure.
 - Stage-4: To inspect anti corrosion painting process of the inner & outer walls of mud tanks and allied accessories.
8. The following grades are required to be selected for each piece of material to be used in fabrication. The grades selected may be according to the length, thickness, quantity (pieces in Kg) and diameter of the materials.
 - 8.1 Metallic Sheet should be M.S Sheets.
 - 8.2. Angles having different lengths & pieces should be A-36 grade.
 - 8.3. Pipes having different lengths & SMLS diameters, 02 grades i.e. A-53 & A-106B should be used.

8.4 Rods having different diameters & lengths, A-36 grade should be used.

9. Top of each tank should be covered with grating & all open sides must be secured with safety hand railings and toe boards.
10. Bidders are required to submit along with the technical bid a list of material with specifications (grade, gauge, schedule, weight, quantity etc.) to be used for fabrication of each part of mud tanks.
11. The bidder will submit detailed procedure of anti-corrosion paint (primary & final coating) elaborating sand blasting for first cleaning & 03 coat of epoxy paint for anti-corrosion/rusting treatment of inside and outer surface of the tanks before final painting.
12. Leak test (hydrostatic test) of all mud tanks will have to be conducted by the supplier before delivery and test reports have to be submitted by the bidder. OGDCL will only accept these tanks if they qualify the test.
13. The mud tanks (10 units) are required to be delivered to OGDCL, at I-9 Base Store Islamabad, in six (06) months starting with effect from acceptance of Purchase Order (P.O).