



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Due Date:

Material :MISC. MATERIAL FOR SLUG CATCHER

Tender Enquiry No: PROC-LD/P&P/17193/18

Bid Bond Value : 92000

Attachment(if any) : YES

EVALUATION WILL BE CARRIED OUT ON FULL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	Level control valve	Detail specification attached	1	Number					
2	Level control valve	Detail specification attached.	1	Number					
3	Pressure differential control valve	Detail specification attached.	1	Number					
4	Pressure safety valve	Detail specification attached	2	Number					

Special Note:- The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- DELIVERY LOCATION: DAKHNI OIL FIELD, DELIVERY PERIOD: 30 DAYS AFTER ISSUANCE OF LPO, PAYMENT: 100% AFTER DELIVERY

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.

Detail for item #1

Pressure Differential control Valve

Type: Globe ; Size: 6" RF 600LB for SOUR Gas service (12%H₂S); Failure class: Failure to close, Operating: Pneumatic operated (3 - 15) PSI,
Control signal: 4-20 mA with complete accessories (Positioner and I/P Convertor), suitable for hazardous area, NACE compliance: Yes, Leakage
Rate: (Class to ASME FCI 70-2) Class VI

Detail for item #2

Level control Valve

Type: Globe size: 2" RF 600LB for SOUR water service (12%H₂S) Failure class: Fail to close,
Operated: Pneumatic operated (3 - 15 PSI) Control signal: 4-20 mA with complete accessories (Positioner and I/P convertor), suitable for hazardous
area, NACE compliance: Yes, Leakage Rate (Class to ASME FCI 70-2) Class VI

Detail for item #3

Level control Valve

Type: Globe Size: 2" RF 600LB for Condensate service (12%H₂S) Failure class: Failure to close, Operated: Pneumatic operated (3 - 15 PSI)
Control signal: 4-20 mA with complete accessories (Positioner and I/P Convertor), suitable for hazardous area, NACE compliance: Yes, Leakage
Rate (Class to ASME FCI 70-2) Class VI

Detail for item #4

Pressure Safety Valves

Ssize 2", Set pressure set point 1450 PSIG and reset Pressure 1425 PSIG, Connection size 2" RF 600LB, Wet parts should be NACE compliance.
(Sour gas)

TERMS AND CONDITION:

- 1- ALL ITEMS SHOULD BE IN ORIGINAL OEM PACKING.
- 2- STANDARD WARRANTY /GURANTTEE FOR ALL ITEMS.
- 3- DELIVERY PERIOD 30 DAYS AFTER THE ISSUANCE OF P.O.
- 4- STANDARD TEST / QUALITY CONTROL DOCUMENT/CERTIFICATES.
- 5- MANUFACTURER SHOULD BE ISO 9001 CERTIFIED.
- 6- CLEARLY AND SEPARATELY MENTION COUNTRY OF ORIGIN, COUNTRY OF MANUFACTURER.
- 7- OEM LITERATURE (ONLY RELEVANT AND HIGH LIGHTED).