



OIL & GAS DEVELOPMENT COMPANY LIMITED  
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD  
SCHEDULE OF REQUIREMENT

Material :SPARES FOR FEED AND SALE GAS COMPRESSOR

Tender Enquiry No: PROC/LH/PT/P&P-17251

Due Date:

EVALUATION WILL BE CARRIED OUT ON FULL

Bid Bond Value : RS. 200,000/-  
Attachment(if any) : YES

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	FUEL REGULATING VALVE, INLET PRESSURE 60PSIG, REGULATING RANGE 15-40PSIG, RATED FLOW 200 <sup>3</sup> /H@40PSIG, CONNECTION TYPE NPT2 F, MODEL NO: 627, MAKE FISHER OR EQUIVALENT	2		Number					
2	PRESSURE SAFETY VALVES, SEAT & PLUG REQUIRED FOR BODY & BONNET: ASTM A216GR.WCB, NOZZLE & DISC: ASTM A182 316, SPRING OPERATED ; -29~200 DEG CELCIUS;3"- 900# RF INLET; 4"- 150# RF OUTLET. (FOR DETAIL SEE ATTACHMENT)	2		Number					
3	PRESSURE SAFETY VALVE, SEAT & PLUG REQUIRED FOR BODY & BONNET: ASTM A216GR.WCB, NOZZLE & DISC: ASTM A182 316, SPRING OPERATED ; -29~200 DEG CELCIUS;1"- 150# RF INLET; 1"- 150# RF OUTLET. (FOR DETAIL SEE ATTACHMENT)	2		Number					
4	RELIEF VALVE OPERATING PRESSURE 2.5MPA, REGULATING RANGE 0.3-2.5MPA, RATED FLOW 63L/MIN, CONNECTION TYPE NPT3/4F, MODEL NO: PB-63, OR EQUIVALENT	2		Number					
5	THERMOSTAT, FLUORORUBBER SEAL, OPEN TEMPERATURE 150 DEG F(65.6 DEG CELCIUS),FULL OPEN TEMPERATURE 170 DEG F(76.7 DEG CELCIUS), CONNECTION TYPE NPT3/4 F, MODEL NO:FPE/A1110V-160, OR EQUIVALENT	2		Number					
6	PRESSURE SAFETY VALVE, SEAT & PLUG REQUIRED FOR BODY & BONNET: ASTM A216GR.WCB, NOZZLE & DISC: ASTM A182 316, SPRING OPERATED ; -29~200 DEG CELCIUS;3"- 600# RF INLET; 4"- 150# RF OUTLET. (FOR DETAIL SEE ATTACHMENT)	2		Number					
7	SDV, PNEUMATIC BALL VALVE ACTUATOR FAIL TO CLOSED SPRING RETURN; PISTON; SINGLE ACTING PNEUMATIC ACTUATOR; BODY:HARD ANODISED ALUMINUM, PISTON:DIE CAST ALUMINUM, PINION:NITRIDE COATED STEEL. (FOR DETAIL SEE ATTACHMENT)	1		Number					
8	ACTUATOR REPAIR KIT REQUIRE ONLY FOR BDV-1103 PNEUMATIC BALL VALVE ACTUATOR ONLY FAIL OPEN; SPRING RETURN; PISTON; SINGLE ACTING PNEUMATIC ACTUATOR; BODY:HARD ANODISED ALUMINUM, (FOR DETAIL SEE ATTACHMENT)	4		Number					
9	ORIFICE PLATE WAFER TYPE, MATING FLANGE: ASME B16.5 2"- 900# WN RTJ, MAX. FLOW:19467NM <sup>3</sup> /H, OPERATING FLOW:15574NM <sup>3</sup> /H, MIN. FLOW:5840NM <sup>3</sup> /H, MODEL: CANALTA, MAKE DANIEL OR EQUIVALENT	2		Number					
10	PCV, 2"-900# RTJ,FAIL OPEN, WITH AIR PRESSURE REGULATORFILTER,BODY: WCB, TRIM: 316, SEAT: 316, SLEEVE: 17-4PH, STEM:316, PACKING: FLEX-GRAPHITE, LEAK	1		Number					



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

Material : **SPARES FOR FEED AND SALE GAS COMPRESSOR**

Tender Enquiry No: **PROC/LH/PT/P&P-17251**

Due Date:

EVALUATION WILL BE CARRIED OUT ON FULL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
11	STAGE:CLASS 4, ACTUATOR: PDL40, POSITIONER: FISHER, (FOR DETAIL SEE ATTACHMENT) ACTUATOR REPAIR KIT REQUIRED ONLY FOR SDV 1102, PNEUMATIC BALL VALVE ACTUATOR ONLY FAIL CLOSED; SPRING RETURN; PISTON; SINGLE ACTING PNEUMATIC ACTUATOR. (FOR DETAIL SEE ATTACHMENT)	4		Number					
12	PRESSURE TRANSMITTER RANGE: 0 TO 1800PSI, MODEL NO: 3051TG4A2B2 1BB4E7M5, MAKE ROSEMOUNT OR EQUIVALENT	2		Number					
13	TEMPERATURE SENSOR IMMERSION LENGTH 225MM, MODEL NO: 0065 C 2 2 D0050 D 0225 T46 A2 E7, MAKE ROSEMOUNT OR EQUIVALENT	2		Number					
14	TEMPERATURE SENSOR IMMERSION LENGTH 115MM, MODEL NO: 0065 C 2 2 D 0050 D 0115 T46 A2 E7, MAKE ROSEMOUNT OR EQUIVALENT	2		Number					
15	TEMPERATURE SENSOR IMMERSION LENGTH 75MM, MODEL NO: 0065 C 2 2 D 0050 D 0075 T46 A2 E7, MAKE ROSEMOUNT OR EQUIVALENT	2		Number					
16	LIQUID LEVEL SWITCH PRECESSION SIZE: 2" , MODEL NO: LS200, MAKE MURPHY OR EQUIVALENT	2		Number					
17	OIL LEVEL CONTROLLER, MODEL NO: LM301-EX, MAKE MURPHY OR EQUIVALENT	2		Number					
18	PNEUMATIC DIAPHRAGM PUMP RATED FLOW:0-3M <sup>3</sup> /H, DELIVERY HEAD 0-70M,COMPRESSED AIR INLET CONNECTION 1/4"NPT F,COMPRESSED AIR OUTLET CONNECTION3/8"NPT F,LIQUID INLET & OUTLET CONNECTION 3/4"NPT F,MODEL NO: RV-53311,MAKE JIANG LNG OR EQUIVALENT	2		Number					
19	DRAIN AUTO CONTROLLER, MODEL NO: LS200NDVOR, MAKE MURPHY OR EQUIVALENT	2		Number					
20	FLOWMETER NORMAL FLOW 15.9MMSCFD, MODEL NO: E+H DO62C1HCCFKNC1RAB 1AAA1AAAKA2 BEBD+PMD75-MBA7881DAA, MAKE E+H OR EQUIVALENT	2		Number					
21	VIBRATION SWITCH, MODEL NO: VS2EXR-24, MAKE MURPHY OR EQUIVALENT	2		Number					
22	VIBRATION TRANSMITTER 24VDC INPUT ; 4-20MA OUTPUT, MODEL NO: ST5484E-153-120-00, MAKE METRIX OR EQUIVALENT	2		Number					
23	DIGITAL NO FLOW TIMER (DNFT), MODEL NO: 10753, MAKE WHITELOCK INSTRUMENTS OR EQUIVALENT	4		Number					



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

Material : **SPARES FOR FEED AND SALE GAS COMPRESSOR**

Tender Enquiry No: **PROC/LH/PT/P&P-17251**

**Due Date:**

EVALUATION WILL BE CARRIED OUT ON FULL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any

**Special Note:-** The prospective bidders also download the master set of Tender Document  
- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.  
- DELIVERY TERM: WITHIN 120 DAYS AFTER ISSUANCE OF LPO ON F.O.R BASIS KORANGI BASE STORE. PAYMENT TERM : 100% AFTER DELIVERY

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.

- COMPRESSOR TAG: K-1110, MAIN EQUIPMENT CAMERON SUPERIOR RAM52, FRAME TYPE :SUPERIOR RAM52; CYLINDER NO.423 (2 x 6.5"), DBL, MAWP 1650PSIG, API- 11P II DIASTANCE PIECE, MAX. SPEED 1200RPM.
- 2) OPERATING PRESSURE: 1245PSIG, SET POINT 1450PSIG, RATED FLOW, MODEL NO: 26JA14-920, MAKE FARRIS OR EQUIVALENT
- 3) OPERATING PRESSURE 40 PSIG, SET POINT 45PSIG, RATED FLOW 16.5MMSCFD, MODEL NO: 26EA10-120, MAKE FARRIS OR EQUIVALENT.
- 6) OPERATING PRESSURE 800PSIG, SET POINT 1000PSIG, RATED FLOW:16.5MMSCFD, MODEL NO: 26JA13A-120, MAKE FARRIS OR EQUIVALENT.
- 7) 24 VDC STAINLESS STEEL SOLENOID VALVE;IEC/UL/ATEX APPROVAL; 2SPDT LIMIT SWITCH WITH BEACON INDICATOR; SIL2 APPROVAL ; ELECTRICAL HAZARDOUS AREA CLASSIFICATION IS CLASS I; GROUP D; DIV.2;EXDIIBT4;IP65; MODEL NO: 6BS6R-P,C40, MAKE NEWAY OR EQUIVALENT.
- 8) PISTON:DIE CAST ALUMINUM, PINION:NITRIDE COATED STEEL; ACTUATOR REPAIR KIT REQUIRE ONLY FOR BDV-1103 PNEUMATIC BALL VALVE ACTUATOR ONLY FAIL OPEN; SPRING RETURN; PISTON; SINGLE ACTING PNEUMATIC ACTUATOR; BODY:HARD ANODISED ALUMINUM,PISTON:DIE CAST ALUMINUM, PINION:NITRIDE COATEDSTEEL;24 VDC STAINLESS STEEL SOLENOID VALVE; IEC/UL/ATEX APPROVAL;2SPDT LIMIT SWITCH WITH BEACON INDICATOR; SIL2 APPROVAL ;ELECTRICAL HAZARDOUS AREA CLASSIFICATION IS CLASS I;GROUP D; DIV.2;EXDIIBT4;IP65; VALVE P/N NEWAY/2BS9J-P,C40 (REPAIR KIT P/N NA), MAKE NEWAY OR EQUIVALENT.

- 10) DVC2000(EXPLOSION PROOFING: EXIA 2 CT4, CONTROL SIGNAL:4-20MA WITH FEEDBACK), IP65, IEC APPROVAL, MODEL NO: 2X50CSC9J-P, MAKE NEWAY OR EQUIVALENT.
- 11) BODY:HARD ANODISED ALUMINUM, PISTON:DIE CAST ALUMINUM, PINION:NITRIDE COATED, STEEL;24 VDC STAINLESS STEEL SOLENOID VALVE; IEC/UL/ATEX APPROVAL;2SPDT LIMIT SWITCH WITH BEACON INDICATOR; SIL2 APPROVAL ;ELECTRICAL HAZARDOUS AREA CLASSIFICATION IS CLASS I; GROUP D; DIV.2;EXDIIBT4;IP65; MODEL NO: 4BS9J-P, C40 (Repair kit P/N NA), MAKE NEWAY OR EQUIVALENT.

**TERMS & CONDITIONS:**

1. OEM AUTHORITY LETTER MUST BE PROVIDED.
2. OEM TO PROVIDE THE CERTIFICATE THAT THE SUPPLIED PARTS ARE BRAND NEW WITH STANDARD WARRANTTEE/GUARANTTEE.
- 3- BIDDER MUST PROVIDE THE SPARES IN STANDARD OEM PACKING.
- 4- EQUIVALENT WILL ONLY BE ACCEPTED ONLY IF COMPATIBLE WITH THE EXISTUING SYSTEM LIKE BASE/SHAPE/DESIGN/CONFIGURATION ETC.