



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

Material : **SUPPLY TESTING & COMMISSIONING OF TRANSFORMER**

**Due Date:**

Tender Enquiry No: **PROC-LD/PT/P&P/17319**

Bid Bond Value : 50000

Attachment(if any) : YES

EVALUATION WILL BE CARRIED OUT ON FULL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	TESTING AND COMMISSIONING JOB OF 2500KVA, 6.6KV/400V, STEP DOWN TRANSFORMER AS STAND BY SOURCE AT UCH 1 PLANT. (COMPLETE JOB IN ALL RESPECTS AS PER ATTACHED SCHEDULE OF REQUIREMENT).	1		Number					
2	SUPPLY OF L.T INCOMING PANEL: WEATHER/ WATER PROOF TYPE, IP65, L.T INCOMER PANEL WITH INTERNAL WIRING. ( THE DETAIL SPECIFICATIONS OF LT PANEL IS MENTIONED IN ATTACHMENT).	1		Number					
3	HT CABLE LAYING, 3C, 120MM2 CU/XLPE/PVC/SWA/PV, CABLE LENGTH 50 METER INSTALLATION OF HT TERMINATION KITS ON HT PANEL AND TRANSFORMER SIDE. ( FOR DETAILS OF JOB SEE ATTACHMENT)	1		Number					
4	SUPPLY OF BUS TIE DUCT WORK: BUS TIE DUCT (BTD), LENGTH: 10 METER, TYPE M.S, BOLTED WITH REMOVABLE SIDE PLATES, 14 SWG ( FOR DETAIL SEE ATTACHMENT)	10		Number					

**Special Note:-** The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- DELIVERY LOCATION: UCH GAS PLANT, DELIVERY PERIOD: 120 DAYS AFTER ISSUANCE OF LPO, PAYMENT TERM: 100% AFTER DELIVERY & COMMISSIONING.

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.





**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

**Mandatory Checklist**

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-A (Un-priced)</b>	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-B</b>	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-D</b>	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-L</b> on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-M</b> on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-N</b> on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-A (Priced)</b>	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-C</b>	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-E</b>	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



- 2) PANEL SIZE: HEIGHT: 7.5 FT X WIDTH: 02 FT X DEPTH: 2.5 FT  
OUTGOING BUS BARS 100MMX12MMX2 (PER PHASE), ENERGY ANALYZER, INDICATION LAMPS, CURRENT TRANSFORMER 3200/5 AMP, POWDER PAINT 7032 14 SWG COMPLETE IN ALL RESPECTS. THE PANEL SHALL BE INSTALLED ON STRUCTURE WITH SUPPORTS COMPLETE IN ALL RESPECTS.
- 3) WINDING RESISTANCE TEST, TRAFO TURN RATIO (TTR) TEST, INSULATION RESISTANCE (IR) TEST, BREAKDOWN VOLTAGE TEST OF TRANSFORMER OIL, DEHYDRATION OF TRANSFORMER OIL, NO LOAD TEST OF TRANSFORMER, LOAD TEST OF TRANSFORMER. SEE ANNEXURE A OF SOR FOR NAME PLATE DATA OF TRANSFORMER AND SNAP OF TRANSFORMER TO BE COMMISSIONED.
- 4) BUS BAR SIZE: 100MM X 12MM X 2(PER PHASE) MOUNTED WITH INSULATORS 125MM X 50MM, BUS BAR RATING: 4000 AMP. POWDER COATED DUCT COMPLETE IN ALL RESPECTS.

SITE VISIT OF PLANT IS NECESSARY BEFORE SUBMISSION OF TECHNICAL OFFER. EXECUTION OF JOB SHOULD BE PERFORMED IN UPCOMING (ATA-2018) OCTOBER 2018.

NOTE: MAIN INCOMING MOTORIZED AIR CIRCUIT BREAKER (ACB), 3POLE, 3200 AMPERE MAKE: TERASAKI FOR LT INCOMING PANEL WILL BE PROVIDED BY OGDCL.

TERMS & CONDITIONS FOR INDENT NO# UCH/ELEC/1431/18

- 1) ALL ITEMS SHOULD BE BRAND NEW AND IN ORIGINAL OEM PACKING
- 2) STANDARD WARRANTY /GURANTTEE FOR ALL ITEMS.
- 3) MANUFACTURER FOR ALL ITEMS SHOULD BE ISO 9001- 2000 CERTIFIED OR HIGHER