SECTION X-X

SECTION C-C

SECTION B-B

DETAIL - `B`

DETAIL - `A`

ITEM	DESCRIPTION	QTY.	MATERIAL
6	1 ½" PIPE COUPLING	1	——
5	1" (25MM) PIPE COUPLING.	8	——
4	1 ¼" NIPPLES.	16	——
3	INTERMEDIATE SUPPORT	32	——
2	ANCHOR BAR ASSEMBLY	8	——
1	SHELL BRACKET	40	——

NOTES:-

1. ITEMS -1 THRU 4 ARE INCLUDED IN VENDOR SUPPLY OF LIQUID LEVEL INDICATORS.
2. THIS DIMENSION TO BE DETERMINED ON SITE BY DROPPING A PLUMB LINE THROUGH AND CONCENTRIC TO ITEM-5
3. INTERMEDIATE BRACES SHOULD BE WELDED TO TANK APPROXIMATELY MIDWAY. EACH PAIR OF SHELL BRACKETS.
4. FOR ORIENTATION OF LIQUID LEVEL INDICATOR OF STORAGE TANKS.

SECTION A-A

Rev. 1	Issue For Fabrication			
Rev. 0	Issue For Approval			
Rev.N0	Revision Note.	Cad By	Checked By	Approved By

OIL & GAS DEVELOPMENT COMPANY LTD.
PROCESS & PLANTS DEPARTMENT
Dakhni Gas Processing Plant

TITLE:- SUPPORTS AND OPENINGS FOR LIQUID LEVEL INDICATORS OF STORAGE TANKS. (N-8)

CAD BY	CHECKED BY	APPROVED BY	DRAWING NO.
SARWAR OBAID Sr.Tech.Officer(Draughting)	Junaid Khan J.E Mech	Hamid Raza Plant Manager	PP / DKN / M / 502 SHEET NO. 15 OF 20
scale NTS	Computer Code PN .014	Rev. 1	Date 02-05-2017