

TECHNICAL SPECIFICATIONS SHEET
OF
LIME STONE POWDER (CALCIUM CARBONATE)

A) TECHNICAL SPECIFICATIONS

SR. NO.	PHYSICAL PROPERTIES	REQUIRED SPECIFICATIONS	EXACT VALUE OF THE OFFERED PRODUCT
01.	APPEARANCE	FREE FROM DIRT AND FOREIGN MATTER	
02.	SPECIFIC GRAVITY (S.G)	2.65 (MINIMUM)	
03.	PERCENTAGE PURITY AS CaCO ₃	95% (MINIMUM)	
04.	SOLUBILITY IN 15% HCl	95% (MINIMUM)	
05.	WATER SOLUBLE CONTENTS	LESS THAN 200 PPM	
06.	RETENSION ON 200 US MESH SIEVE	LESS THAN 05% BY WEIGHT	