



1/4

**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

Material : **SMOKE & HEAT DETECTORS**

Tender Enquiry No: **PROC/LG/PT/HSE-17958 - (A)**

**Due Date:**

EVALUATION WILL BE CARRIED OUT ON FULL

Bid Bond Value : 120,000/=

Attachment(if any) : YES

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	Intelligent Heat Detector compatible with Fike Fire Alarm and Detection System (Data Sheet attached) with 4 inch base	10		Number					
2	Intelligent Photoelectric Smoke Detector compatible with Fike Fire Alarm and Detection System (Data Sheet attached) with 4 inch base	140		Number					

**Special Note:** The prospective bidders also download the master set of Tender Document  
- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.  
- BID VALIDITY IS 120 DAYS FROM TECHNICAL BID OPENING. DELIVERY WITHIN 180 DAYS AT I-9 BASE STORE ISLAMABAD.  
PAYMENT WILL BE MADE AFTER DELIVERY AND INSPECTION.

Discount (if any) shall only be entertained on Schedule of Requirement of Bidding Document (Financial Proposal). If the discount is mentioned elsewhere in the bid, the same shall not be entertained.



Handwritten initials/signature

**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

**Mandatory Checklist**

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes	No
Original Bid Bond	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-A (Un-priced)</b>	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-B</b>	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-D</b>	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-L</b> on Company's Letterhead	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-M</b> on Company's Letterhead	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-N</b> on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-A (Priced)</b>	Financial Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-C</b>	Financial Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-E</b>	Financial Bid	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>



3/14

**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No.of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) \_\_\_\_\_

4/4

## SPECIFICATIONS

### Heat Detectors

Device	Intelligent Heat Detector (P/N 60-1039) with detector base
Type	Fixed temperature/rate-of-rise detector
Set-point range	135-170°F for ordinary detection, or 175-190°F for intermediate detection. Detectors in the intermediate range may be programmed for either fixed or 15°F rate-of-rise application.
Design	Designed with tri-color LEDs to indicate detector status.
Compatibility	Compatible with Fike's CyberCat® and Cheetah® Xi intelligent control panels. Its operating parameters should be configured using the panel's programming software and stored within non-volatile RAM in the detector
Normal Operating Voltage	15 to 30 VDC
Standby Current	215 mA max. @ 24 VDC (continuous broadcasts)
LED Current	2 mA max. @ 24 VDC (LEDs on)
Operating Humidity Range	10% to 93% Relative Humidity Non-condensing
Installation Temperatures	-4 to 100°F (-20 to 38°C); 135 - 174°F setpoint -4 to 150°F (-20 to 66°C); 175 - 190°F setpoint
Fixed Temperature Rating	135°F (57°C) 190°F (88°C); programmable
Rate of Rise Detection	Responds to greater than 15°F/min.(8°C/mm); programmable

### Smoke Detectors

Device	Intelligent Photoelectric, spot-type smoke detectors, (P/N 63-1052) with detector base
Type	Having sensing chambers that utilize the light scattering principle to detect smoke.
Design	Designed with tri-color LEDs to indicate detector status.
Compatibility	Compatible with Fike's CyberCat® and Cheetah® Xi intelligent control panels. Its operating parameters should be configured using the panel's programming software and stored within non-volatile RAM in the detector.
Normal Operating Voltage	15 to 30 VDC
Standby Current	481µA max. @ 24 VDC (continuous broadcasts)
Alarm Current	2 mA max. @ 24 VDC (LEDs on)
Humidity Range	10% to 93% Relative Humidity, non-condensing
Temperature Range	32°F to 120°F (0°C to 49°C)