



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL ISLAMABAD)
SCHEDULE OF REQUIREMENT

Material :52 SEATER BUS AC

Due Date:

Tender Enquiry No: **PROC:LE/PT/CSR-18091**

Bid Bond Value : PKR.300000/-

EVALUATION WILL BE CARRIED OUT ON FULL

Attachment(if any) : NIL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	52 Seater Bus (A/c) (Detail is Attached)	1		Number					

Special Note: The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- TO BE DELIVERED AT BASE STORE, I-9 ISLAMABAD, WITHIN 120 DAYS FROM THE DATE OF ISSUANCE OF LPO. PAYMENT WILL MADE AFTER DELIVERY. BID VALIDTY IS 120 DAYS AFTER TECHNICAL BID OPENING.



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL) ISLAMABAD
SCHEDULE OF REQUIREMENT

Mandatory Checklist

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-A (Un-priced)	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-B	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-D	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-L on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-M on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-N on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-A (Priced)	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-C	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-E	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL) ISLAMABAD
SCHEDULE OF REQUIREMENT

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No.of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) _____

**SPECIFICATION OF AC BUSES FOR INDENT # TPT/2013/08****1. AC BUSES 45 SEATER: FULLY EQUIPPED AS PER HSEQ STANDARD:**

BRAND NEW LATEST MODEL, RIGHT HAND DRIVE, AC BUS 45 SEATER, DIESEL ENGINE EURO II 11,000 CC DISPLACEMENT (MIN), 320 ± 10% HP , FITTED WITH ABS BRAKES , FULLY EQUIPPED AS PER HSEQ STANDARD.

1.1. STEERING POSITION:

RIGHT HAND DRIVE

1.2. ENGINE:

- REAR SIDE,
- DIESEL ENGINE EURO-II,
- 4 CYCLE,
- 6 CYLINDER , IN-LINE TYPE
- DISPLACEMENT 11,000 CC
- 320 ± 10 % HP ENGINE ,
- WATER COOLED TURBO CHARGED INTERCOOLED.
- ECONOMICAL FUEL CONSUMPTION RATE.
- DUAL TYPE AIR CLEANER

1.3. BODY:

- RIVETLESS SKELETON STEEL BODY,
- SEATS 45 RECLINING TYPE WITH FOLDING ARM REST,
- EXTERIOR AND ROOF SIDE STEEL SHEET,
- SAFETY BELT TO EACH SEAT (REEL TYPE),
- FOLDING SEAT FOR CONDUCTOR,
- DOORS AT ENTRANCE AND EXIT (EMERGENCY),
- ROOF AIR VENTILATOR,
- BODY PANELING HEAT INSULATION EXTERIOR AND ROOF SIDE STEEL SHEET.

1.4. AIR CONDITIONER:

ROOF-ON HEAVY DUTY TYPE (28000KCAL/H)

1.5. BRAKES:


- SERVICE BRAKES (FULL AIR FOUR CIRCUIT BRAKE SYSTEM)
- PARKING BRAKE (SPRING CHAMBER TYPE)
- AUXILIARY BRAKE (EXHAUST BRAKE)

1.6. FUEL TANK:

- 320 LTR (MIN)

1.7. ELECTRIC SYSTEM:

- BATTERY (12 DC /MF-150 AH, 2 EA)
- ALTERNATOR (24 V DC/150 AMP)
- STARTER (24 V DC/6.0 KW)


M. ARSHAD
Social Welfare Officer
Ext: 2197

**1.8. METER & GAUGE:**

- TACHOGRAPH, SPEEDOMETER, ODOMETER
- AIR PRESSURE GAUGE
- FUEL GAUGE
- TACHOMETER (RPM METER), VOLT METER
- WATER TEMPERATURE GAUGE
- ENGINE OIL PRESSURE GAUGE

1.9. SEATS:

- DRIVER SEAT (AIR SUSPENSION TYPE VINYLE LEATHER COVERING) & SEAT BELT 3 POINT WITH ALARM
- CONDUCTOR SEAT (FOLDING TYPE)

1.10. STANDARD ACCESSORIES:

- ABS (ANTI-LOCK BRAKING SYSTEM)
- ROOF-ON EMERGENCY LIGHT,
- WARNING REFLECTOR TRIANGLE FOR EMERGENCY SITUATION,
- METAL TOOL BOX,
- TOOL KIT WITH AIR GUN,
- 02 NO'S UNITS ESCAPE HAMMER FOR EMERGENCY GLASS BREAK,
- FIRE EXTINGUISHER ,
- FOLDABLE SUN SHADE ON BOTH SIDES OF WIND SCREEN,
- FOLDABLE CURTAINS
- HOT AND COLD UNIT WITH DUAL RAIL,
- SEAT COVERS
- SEATS MOUNTED ON ADJUSTABLE RAIL
- SPARE WHEEL WITH ALLOY RIM

2. TERMS & CONDITIONS :

- i. PROVIDE DETAILED SPECIFICATIONS, BROCHURES OF THE MANUFACTURER IN ORIGINAL ALONG WITH THE BID.
- ii. THE INDENTING BIDDER & ITS PROPOSED MANUFACTURER MUST HAVE A MIN EXPERIENCE OF 15 YEARS.
- iii. AVAILABILITY OF SPARES/AFTER SALES SERVICE IN PAKISTAN HAS TO BE ENSURED. FIRMS MUST ATTACH ADDRESSES OF THEIR WORKSHOPS /AUTHORIZE WORK SHOPS, TELEPHONE /FAX NO, WITH THE OFFER, WITHOUT WHICH THE BID WILL BE REJECTED. THEY MUST HAVE QUALIFIED SERVICE ENGINEERS AND TECHNICIANS ON THEIR COMPANY'S PAYROLL.
- iv. MANUFACTURERS OR AUTHORIZED DEALERS HAVING SOUND AFTER SALES SERVICE ARE ONLY ALLOWED TO OFFER BIDS.
- v. THE BIDDERS MUST PROVIDE SPECIFICATIONS OF EACH ITEM IN THE SCHEDULE OF REQUIREMENT (COMPARISON OF TECHNICAL SPECS MUST BE PROVIDED)
- vi. ALL THE BIDDERS ARE ADVISED TO COMPLY STRICTLY TENDER SPECIFICATIONS AND NO DEVIATION SHALL BE ALLOWED.
- vii. SUPPLIER WILL PROVIDE COMPLETE WORKSHOP MANUAL AND PARTS CATALOG.
- viii. WARRANTY PERIOD OF TWO YEARS AFTER DELIVERY OF ITEMS.
- ix. DELIVERY PERIOD : . . MONTHS

FOUR