



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

**Due Date:**

Material :

Tender Enquiry No: **PROC-LD/PT/P&P/18356**

Bid Bond Value : 131400

Attachment(if any) : YES

EVALUATION WILL BE CARRIED OUT ON FULL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	Services required for 4 Inch Diameters Bore , width of road is 20 feet (Please see attached Terms and Conditions)	6		Number					
2	4 Inch Diameter Conduit of 20 feet (Please see attached terms and conditions)	6		Number					
3	8 Channel Network Video Recorder with 10TB Segate surveillance HDD (Make :Dahua DH-NVR-51084K-S2) OR EQUIV.	1		Number					
4	Concrete Base Installation of Poles for Cameras along with Civil work foundation 3 feet deep x 1' x1' for pole with Nut bolts and base plate	4		Number					
5	DATA CABINET DOUBLE SECTION 4 U : Dimensions: Height 11 inch, Width 23.5 inch, Depth 17.75 inch, Mounting Depth 15.70 Inch with 8 Socket PDU,Double Section, Front Tinted Glass Door with Lock, 1 Fan, White Color (Make Orient or equivalent)	1		Number					
6	Soft digging 3 Feet deep and 6 inch width, 500 meter length which includes services for fiber and power cable laying with HDPE Pipe and concrete backfill with a layer of sand and a layer of bricks with warning tape and warning plates	1		Number					
7	SC/SC SM Duplex Fiber Patch Cord 3 Meter Make: DLINK OR EQUIVALENT	12		Number					
8	Fiber Optic Cable laying in cable tray of 700 metres fitting with pvc clumps/cable ties etc	1		Number					
9	Fiber Joints Kit (24 Core) ,Joint Enclosure Box ,Optical Cable Splice Closure, the protection level ip-66, temperature ranges from -40 centigrade to 65 C OR EQUIV.	1		Number					
10	HDMI Cable from NVR to LED Display screen (30 ft) 4K Original Copper Fiber Cable Make : ULT -Unite OR EQUIVALENT	2		Number					
11	Complete installation of 04 Explosion proof PTZ Camera on a pole and commissioning of network in all aspects (Please see attached Layout Diagram of Cameras Location).	4		Number					
12	Aluminum Alloy pole mount bracket for Camera (2ft) with accessories ( to be fix on Pole).The maximum load capacity of the bracket is 30 KG OR EQUIV.	4		Number					
13	Junction BOX Explosion Proof, Size: 10X10 inch (for MC and ODF), Degree of Protection IP66 ,Explosion proof standard is EX II 2 G Ex db eb ia/ib mb IIA, IIB, IIC T4 (Ta= - 60 - +70 C), Make : STAHL ,Model: 8150/1-0300-0200-150-3311 OR EQV.	4		Number					



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

**Due Date:**

Material :

Tender Enquiry No: **PROC-LD/PT/P&P/18356**

EVALUATION WILL BE CARRIED OUT ON FULL

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
14	30 Feet Tapered Anchor Pole above the ground level, Galvanized Round Pipe (thickness: 12 gauge, 5 Inch Wide 15feet & 4inch wide upper portion) with Foundation Civil work and installation/Erection	4		Number					
15	Fiber ODF 12 port Rackmount With accessories Make : DLINK OR EQUIV.	1		Number					
16	Fiber ODF 12 port Outdoor with all accessories Make : DLINK OR EQUIV.	4		Number					
17	CAT 6 FTP Cable , 23 AWG UV Resistant Outdoor Cat 6 Bulk Cable , Allows operation in 75C ambient environment providing error-free performance in high-density cabinets and large cable bundles ,FTP cat 6A ,Make : 3M / Schneider OR EQUIV.	80		Feet					
18	STAINLESS STEEL Pipe Dia 1 Inch with stainless steel Glands Accessories (2 Steel Glands will be used with Junction Box 1 Input & 1 output)(Complete from JB to Camera)	80		Feet					
19	12 Core Single Mode Optical Fiber Cable , Fiber proof test level : 0.70 Gpa 100(1%) (kpsi) , Zero dispersion wavelength : 1300-1322 nm, Loss performance at 1550 nm:0.1 dB loss , Conforming to ITU-T G652 Standard ,Make : Premier or Equiv.	1200		Meter					
20	Media Converter with SFP Module, Explosion Proof (pairs) (Make : JHA-EXIG11WM (China) or equivalent	4		Number					
21	HDPE PIPE 1.5" (For Fiber Burried), High Density Polyethylene ,ISO : 4427, Outside Dia : 1.9 Inch , Wall thickness 0.173.(Make : Jamal Pipes/ Master Pipes ) or equivalent	500		Meter					

**Special Note:** The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- BID VALIDITY: 120 DAYS AFTER TECHNICAL BID OPENING. DELIVERY LOCATION: QADIRPUR GAS FIELD, DELIVERY PERIOD: 120 DAYS AFTER ISSUANCE OF LPO, PAYMENT TERM: 100% AFTER DELIVERY AND INSTALLATION.



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

**Mandatory Checklist**

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-A (Un-priced)</b>	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-B</b>	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-D</b>	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-L</b> on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-M</b> on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped <b>Annexure-N</b> on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-A (Priced)</b>	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-C</b>	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped <b>Annexure-E</b>	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD**  
**SCHEDULE OF REQUIREMENT**

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No. of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) \_\_\_\_\_

Scope Of Work / Terms & Conditions for Installation Material of Explosion Proof Cameras including Hiring of Services.

1. PPE's will be arranged by the contractor.
2. Equivalent Items will be accepted and should be compatible in every aspect with respect to the required model.
3. Payment will be made as per actual job performed and activity wise detail breakup in terms of finance should be provided in Financial bid. Also confirmation regarding activity wise detail breakup in terms of finance should be confirmed in technical bid.
4. Technical Literature of required items will be provided by the Bidder.
5. OGDCL will provide boarding & lodging
6. OGDCL will provide Welding Plant.
7. OGDCL will provide lifting facility from Instruments workshop/store to site.
8. OGDCL will provide Crane for Installation of Instruments.
9. OGDCL will provide Electric Power & lightening if required
10. Contractor will ensure cleaning and housekeeping of related areas after job completion
11. 04 Explosion proof Cameras PTZ HL-E9001-1080 are already purchased and services for installation and successful commissioning along with material are needed for these cameras.
12. CV's of qualified individuals will be provided by the bidder.
13. For any Ambiguity regarding Scope of Work , the bidder can contact Incharge Instrument Section OGDCL Qadirpur Gas field at 0723-660729 before submission of bids.