



Yu

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Material :FIRE ALARM SYSTEM

Due Date:

Tender Enquiry No: PROC-LD/PT/P&P-18398

Bid Bond Value : RS:- 65,000/=

EVALUATION WILL BE CARRIED OUT ON FULL

Attachment(if any) : YES

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	Heat detector (details attached)	3		Number					
2	Installation,Testing and commissioning services.	1		Unit					
3	Manual call point (details attached)	12		Number					
4	Optical smoke detector (details attached)	200		Number					
5	Remote keypad (details attached)	3		Number					
6	Single loop compact analogue-addressable control panel (details attached)	3		Number					
7	Visual/audible alarm indicator (details attached)	12		Number					

Special Note: The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- DELIVERY WITHIN 120 DAYS AFTER LPO AT DHAKNI PLANT. BID VALIDITY 150 DAYS AFTER TECHNICAL BID OPENING 100% PAYMENT WILL BE MADE AFTER DELIVERY, INSTALLATION AND COMMISSIONING.

Remote keypad :
 should connect to a HORNET+ network (double RS485 connection); Protection Grade: IP 30.
 CPR EN54-2, EN54-4, EN54-13, CPR EN54-21, EN12094-1

Single loop compact analogue-addressable control panel :
 Capable of managing 240 points. Multiprotocol, manages, Inim, Apollo and Argus security protocols on the loop. 1,5 A integrated power supply. 2000 event memory. Protection Grade IP 30. Certified CPR EN54-2, EN54-4, EN54-13,

Optical smoke detector:
 UL-EU, LPCB Approved. Sensitivity configurable as 0.08dB/m; 0.10dB/m; 0.12dB/m; 0.15dB/m. Degree of protection: IP43

Heat detector :
 UL-EU, LPCB Approved; Heat detector can be configured in the following modes: A1R mode (fixed threshold at 58°C with thermogeometric detection); B mode (fixed threshold at 72 deg C; A2S mode (fixed threshold at 58degC); BR mode (fixed threshold at 72 deg C with thermogeometric detection). Degree of protection: IP43

Manual call point :
 Manual callpoint with resettable element operated by plastic key (included). LPCB CPR EN54pt11/pt17

Visual/audible alarm indicator :
 Should have red casing; IP Protection grade IP65. ; (IP21 EN54-3 certified) ; Sound output @ 1m MAX 101 dB.; Operating voltage 18-30 Vdc. ; EN 54-3, EN 54-17, EN 54-23, 0051-CPR-1316, 0051- CPR- 1317, CE.

Fire resistant cable:
 Fire resistant cable 2 core 1.5mm.

Installation, Testing and commissioning services:
 installation, testing and commissioning of the complete material on turn key basis.

Deliverables:
 1- Bidder to provide all types of drawing (wiring diagram, job drawings etc)
 2- Cause & effect drawings.
 3- Any other technical information related to project.

TERM AND CONDITION.

1. Parts must be in original OEM Packing.
2. Parts must be new & free from any defect.
3. Parts must have standard OEM warranty/guarantee.
4. Delivery period is 120 days from date of issuance of P.O.
5. Bidders to submit their company profiles, experience for supply of such spare parts (i.e. Previous Purchase Orders) along with technical bids.
6. System to be provided must have at least one year warranty/guarantee for equipment after installation.
7. System to be provided must conform to related NFPA standards such as NFPA 3 and NFPA 92



73/4

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Mandatory Checklist

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-A (Un-priced)	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-B	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-D	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-L on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-M on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-N on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-A (Priced)	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-C	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-E	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



Handwritten signature or initials inside a circle.

**OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT**

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No.of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) _____