



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Material : **BUS, 45 PASSENGER SEATS**

Tender Enquiry No: **PROC/LE/PT/18421/21**

EVALUATION WILL BE CARRIED OUT ON FULL

Due Date:

Bid Bond Value : **RS.400,000/-**

Attachment(if any) : **YES**

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	45 PASSENGER SEATS AC BUS (DETAIL IS ATTACHED).	1		Number					

Special Note: The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- BID VALIDITY 120 DAYS FROM TECHNICAL BID OPENING. DELIVERY IN 120 DAYS FROM LPO ISSUE DATE ON FOR I-9 BASE STOP ISLAMABAD.PAYMENT AFTER DELIVERY & INSPECTION AT SITE.



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Mandatory Checklist

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-A (Un-priced)	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-B	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-D	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-L on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-M on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-N on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-A (Priced)	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-C	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-E	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No. of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) _____

Specification of AC Bus

1. Ac Bus 45 seater: Fully equipped as per HSEQ standard:

Brand new latest Model, Right hand drive, Manual transmission, AC bus 45 seater, diesel engine turbo charged/Euro II, intercooled, 7500 cc displacement (min), 235 ± 10% HP , fitted with service, auxiliary & parking brakes , fully equipped as per HSEQ standard.

1.1. Steering Position:

- Right hand drive (4x2)
- Power steering
- Telescopic and tilt steering column with locking device

1.2. Engine:

- Rear side or Front side,
- Diesel Engine Turbo charged/Euro-II, intercooled
- 4 cycle,
- 6 Cylinder , IN-LINE Type
- Displacement 7500 cc (min)
- 235 ± 10 % HP Engine ,
- Water cooled Turbo charged intercooled.
- Economical fuel consumption rate.
- Dual Type Air cleaner

1.3. Body:

- Rivetless skeleton steel body OR Principal framework of hollow square and rectangular M.S tubes,
- Exterior and roof side steel sheet,

- Folding type Auto door with toughened and fixed glasses and have with 2-3 entrance steps
- Roof air ventilator,
- Body paneling heat insulation exterior and roof side steel sheet.
- Overall length: 10,000 mm(min)
- Ground clearance: 200 mm(min) at rear axle
- Defogger/defroster for wind screen
- 7 Nos tires (including one spare tire)
- Suspension with hydraulic double acting telescopic shock absorbers

1.4. Air conditioner:

- Roof-on heavy duty type (min 20000Kcal/H)

1.5. Brakes:

- Service Brakes (Full Air four Circuit Brake System/ Air over Hydraulic)
- Parking Brake (Spring Chamber Type/ Mechanical)
- Auxiliary Brake (Exhaust Brake)/ Electro Pneumatic

1.6. Fuel Tank:

- 200 LTR (min)

1.7. Electric System:

- Battery (12 DC /MF-100-150 AH, 2 in series connection)
- Alternator (24 V DC/60-150 AMP)
- Starter (24 V DC/6.0 KW)

1.8. Meter & Gauge:

- Tachograph, Speedometer, Odometer
- Air pressure guage
- Fuel Gauge
- Tachometer (RPM meter), Volt meter

- Water Temperature Gauge
- Engine oil pressure Gauge

1.9. Seats:

- 45 seats (with individual bottom and back covered with velvet and rexine, 2x2 configuration)
- Safety belt to Drivers seat and front passengers seat
- Folding seat for conductor,

1.10. Transmission

- Manual with atleast five forward + one reverse (5+1)

1.11. Standard Accessories (min):

- Roof-on emergency light,
- Metal tool box,
- Tool kit with air gun,
- Fire extinguisher
- First aid kit
- Foldable sun shade on both sides of wind screen,
- Foldable curtains
- Seat covers
- Seats mounted on adjustable rail
- Spare wheel with Alloy Rim
- Room lights
- Reverse light
- Room heater(Floor mounting type)
- Fog lights