

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION E

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material GRINDING MILL
 Tender Enquiry No PROC-FE/CB/G&R LABS-3111/2017
 Due Date
 Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY AIR	Total Price C & F BY AIR	Deviated From Tender Spec. If Any
1	Grinding Mill for sample preparation of RE-6 and TOC analyzer (Details attached)	Number	1					

Suitable for the Grinding of 10-20 gm Rock Samples

Full
 Dr. Saad Abbas
 Chief Chemist (R&D) (S)
 Exploration, Research Deptt.
 OGDCL, Islamabad

Note:

- 1) PURSUANT TO TENDER CLAUSE # 2, 13 & 35.3.2, BID BOND AMOUNTING TO **US\$ 250/-** (US DOLLAR TWO HUNDRED FIFTY ONLY) OR EQUIVALENT TO PAK RUPEES MUST BE SUBMITTED WITH THE TECHNICAL BID.
- 2) EVALUATION CRITERIA: **FULL CONSIGNMENT WISE (EXCEPT RECOMMENDED SPARES)** ON C&F BY AIR, ISLAMABAD. **UNIT PRICE OF EACH RECOMMENDED SPARE TO BE QUOTED SEPARATELY IN THE FINANCIAL BID ONLY.**
- 3) **TERMS AND CONDITIONS:** BIDDERS ARE ADVISED TO CAREFULLY READ ALL THE TERMS AND CONDITIONS OF THE TENDER DOCUMENT AVAILABLE AT OGDCL WEBSITE IN THE MASTER TENDER DOCUMENT.
- 4) **SHIPMENT FROM ACU MEMBER COUNTRIES:** IN CASE OF SHIPMENT FROM ACU MEMBER COUNTRIES, THE LC BENEFICIARY SHOULD BE OF THAT PARTICULAR COUNTRY FROM WHERE THE CONSIGNMENT IS BEING SHIPPED.
- 5) **SUMMARY REJECTION CRITERIA:** THE SUMMARY REJECTION CRITERIA AT CLAUSE 35 OF THE TENDER DOCUMENT MAY ALSO BE EXAMINED CAREFULLY. ANY BID NOT MEETING THE CRITERIA SPELLED IN THE CLAUSE # 35 SHALL BE SUMMARILY REJECTED WITHOUT ANY RIGHT OF APPEAL.
- 6) DETAIL TECHNICAL SPECS SHEET ATTACHED.
- 7) DELIVERY PERIOD : 30 DAYS FROM LC

Grinding Mixer Mill for grinding and homogenize mixing of small quantity of rock samples. Can be used for wet grinding as well. Maximum reproducibility, bench top, for sample quantity 10-20 gram rock sample or up to 20 mL sample volume, ~5mm size sample feed, minimum Two(02) grinding module works simultaneously, grinding through horizontal vibration of sample with grinding balls, with quick damping device, grinding martial size 10micron or better, Grinding time 2-3 minutes or better, safety locking and other security features for maximum protection, digital time and parameter adjustment buttons, operating electrical condition 220 VAC 50-60 Hz, 120-200 Watt, operating ambient temperature 10-45 degree Celsius, Suitable two (02) pair of Stainless steel(S.S) pot or jars for up to 10gm rock sample, Suitable two (02) pair of S.S pot or jars up to 20 gm rock sample, suitable stainless steel ball diameter size 20mm(04 Nos.), 15mm(08 Nos.), 12mm(12 Nos.) and 10mm(16 Nos.), Two(02) safety glass, Two Seives 60mesh, Two(02) grinding pot /jar tongs, power cord, one(01) safe power extension box, factory certificate, operation qualification(OQ) documents, all manuals and standard accessories, machine cover, onsite one (01) week training, Two (02) years parts and labor warranty.

1. Billie