

**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT, ISLAMABAD**  
**FOREIGN SECTION B**

(To be completed, filled in, signed  
and stamped by the principal)

**ANNEXURE 'A'**

**Material** BRIDAL LINES FOR RIG N-5 & N-6  
**Tender Enquiry No** PROC:FB/CB/D-4139/2018  
**Due Date**  
**Evaluation Criteria** FULL

**SCHEDULE OF REQUIREMENT**

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	BRIDAL LINE FOR MAST RAISING/LOWERING( FOR M/S RG PETRO, CHINA RIG MAST PART # JJ-45045-32-01-00), DIA 72mm, Length 61.5 Meter (02 pieces = 01 set), DETAIL DESCRIPTION ATTACHED.	Number	4					
2	BRIDAL LINE FOR M/S RG PETRO CHINA RIG FLOOR (RG RIG FLOOR PART # DZ70-34-02-00), DIA 42 mm, Length 40.5 Meters ( 02 pieces = 1 set).DETAIL DESCRIPTION ATTACHED.	Number	4					

**Note:** NOTE: PAYMENT WILL BE MADE AS PER THE FOREIGN PROCUREMENT PAYMENT TERMS AVAILABLE AT OGDCL WEBSITE (TENDERS TAB) EFFECTIVE FROM FEBRUARY 27, 2018.  
 NOTE:02; PURSUANT TO TENDER CLAUSE # 2.2, 11.4, 13 & 35.3.2, BID BOND OF USD1,500/- IS TO BE SUBMITTED IN USD OR EQUIVALENT PAK RUPEES MUST BE SUBMITTED WITH THE TECHNICAL BID AND VALID FOR 150 DAYS FROM THE DATE OF OPENING OF THE BID.

*indent*

GENERAL TERMS & CONDITIONS.

1. THE MANUFACTURER OF WIRE ROPE MUST HAVE APPROVAL OF API SPECS 9A FOR THE LAST TWENTY FIVE (25) YEARS AS WIRE ROPE MANUFACTURER. IN THIS REGARD LATEST & CONSECUTIVE TWENTY FIVE (25) YEARS BACK API 9-A CERTIFICATES MUST BE SUBMITTED WITH THE TECHNICAL OFFER OR PROOF FROM API OFFICIAL WEBSITE TO BE SUBMITTED.
2. THE OFFERED DRAW WORKS/RIG FLOOR & MAST RAISING/ LOWERING LINES MUST BE SUITABLE FOR USE AT M/S RG PETRO CHINA MAKE RIGS OF OGDCL I.E. FOR M/S RG PETRO, CHINA RIG MAST PART # JJ-45045-32-01-00), DIA 72MM, LENGTH 61.5 METER AND FOR RIG FLOOR PART # DZ70-34-02-00), DIA 42 MM, LENGTH 40.5 METERS.
3. DETAILED TECHNICAL LITERATURE OF THE OFFERED DRAW WORKS/RIG FLOOR & MAST RAISING/ LOWERING LINES AND END FITTINGS (NAME OF MANUFACTURER, PART NUMBER, MODEL NUMBER, NOMENCLATURE, TYPE OF LAY, GRADE OF ROPE, BREAKING STRENGTH, SIZE AND LENGTH OF EACH PIECE ETC.) MUST BE SUPPLIED WITH THE PROPOSAL.
4. THE OFFERED WIRE ROPE MUST CONFORM TO API-9A/EQUIVALENT ISO SPECIFICATIONS. END FITTINGS MUST BE ACCORDING TO API RECOMMENDED PRACTICE 9B (API RP9B) OR ISO 17558:2006 (STEEL WIRE ROPES SOCKETING PROCEDURES).
5. THE OFFERED WIRE ROPES MUST BE SUPPLIED FROM FRESH STOCK AND MUST BE BRAND NEW AND UNUSED. CONFIRMATION TO THIS EFFECT MUST BE PROVIDED WITH THE PROPOSAL.
6. THE DRAW WORKS/RIG FLOOR & MAST RAISING/ LOWERING LINES MUST BE PACKED IN A SAFE & COMPACT MANNER TO AVOID ANY DAMAGE DURING SUPPLY/ TRANSPORTATION.
7. LETTER IN ORIGINAL FROM THE MANUFACTURER(S) COVERING WARRANTY/GUARANTEE FOR OFFERED WIRE ROPES FOR A PERIOD OF 18 MONTHS FROM DATE OF SHIPMENT WITH TENDER ENQUIRY NUMBER MUST BE FURNISHED WITH THE TECHNICAL OFFER.
8. THE SUCCESSFUL BIDDER WILL BE REQUIRED TO FURNISH MILL INSPECTION CERTIFICATE FOR ALL WIRE ROPES WITH SHIPPING DOCUMENTS. CONFIRMATION TO THIS EFFECT MUST BE PROVIDED IN THE TECHNICAL OFFER.
9. AUTHORITY LETTERS IN ORIGINAL FROM THE MANUFACTURER(S) TO BIDDER AND FROM BIDDER TO LOCAL AGENT FOR OFFERED WIRE ROPES WITH TENDER ENQUIRY NUMBER MUST BE FURNISHED WITH THE TECHNICAL OFFER. THE AUTHORITY LETTER MUST BE ON COMPANY LETTER HEAD, SHOWING THE NAME AND CONTACT DETAILS (E-MAIL & FAX NUMBER) OF THE SIGNING AUTHORITY.
10. ORIGINAL BROCHURE OR BROCHURE ON CD FORMAT OF THE MANUFACTURER(S) CONTAINING TECHNICAL LITERATURE/SPECS SHEETS SPECIFYING PHYSICAL/PERFORMANCE PROPERTIES OF QUOTED WIRE ROPES MUST BE SUBMITTED WITH THE TECHNICAL OFFER.
11. THE MANUFACTURER SHOULD HAVE MINIMUM TWENTY FIVE (25) YEARSS EXPERIENCE IN THE MANUFACTURING OF WIRE ROPES AND HAVE SUPPLIED WIRE ROPES EACH YEAR DURING LAST 10 YEARS TO THE MAJOR INTERNATIONAL E & P COMPANIES LIKE EXXON, PDO, KOC, SHELL, BP, TOTAL, ENI, MOL, OMV OR EQUIVALENT AND DRILLING CONTRACTORS COMPANY LIKE SCHLUMBERGER, WEATHERFORD, EXALO



ETC. IN THIS REGARD BIDDER(S)/ MANUFACTURER SHOULD PROVIDE LAST 10 (TEN) YEARS COMPREHENSIVE DETAILED SUPPLY RECORD CONTAINING DETAIL OF OFFERED AND SIMILAR WIRE ROPES SIZE, QUANTITY, NAME OF CUSTOMERS OTHER THAN MANUFACTURERS OWN COUNTRY SHALL BE SUBMITTED WITH THE TECHNICAL OFFER. IN THIS REGARD UNPRICED COPIES OF AT LEAST 10 DIFFERENT PURCHASE ORDERS FOR WIRE ROPES OTHER THAN MANUFACTURERS OWN COUNTRY SHOULD ALSO BE SUBMITTED WITH TECHNICAL BID. THE SUPPLY RECORD MUST BE ON THE COMPANY LETTERHEAD AND SHOULD INDICATE THE NAME & DESIGNATION OF THE SIGNING AUTHORITY ALONG WITH HIS COMPLETE CONTACT DETAILS PHONE & FAX NUMBERS AND HIS OFFICIAL EMAIL ADDRESS.

12. IF MANUFACTURER HAS NOT ALREADY SUPPLIED WIRE ROPES (DRILL LINES) TO OGDCL THEN CERTIFICATES OF SATISFACTORY PERFORMANCE FOR DRILL LINES TO BE ISSUED BY AUTHORIZED OFFICIAL(S) OF AT LEAST 3 (THREE) DIFFERENT RENOWNED INTERNATIONAL E&P COMPANIES LIKE SAUDI ARAMCO, PDO, KOC, SHELL, BP, TOTAL, ENI, MOL, OMV OR EQUIVALENT AND DRILLING CONTRACTORS COMPANY LIKE SCHLUMBERGER, WEATHERFORD, EXALO ETC IN FAVOUR OF MANUFACTURER SHOULD BE SUBMITTED WITH THE TECHNICAL OFFER. IF MANUFACTURER HAS ALREADY SUPPLIED WIRE ROPES (DRILL LINES) TO OGDCL THEN ITS PERFORMANCE WILL BE EVALUATED ON IN HOUSE REPORT. THE CERTIFICATES MUST BE ON THE COMPANY LETTERHEAD AND SHOULD INDICATE THE NAME & DESIGNATION OF THE SIGNING AUTHORITY ALONG WITH HIS COMPLETE CONTACT DETAILS PHONE & FAX NUMBERS AND HIS OFFICIAL EMAIL ADDRESS. HOWEVER ABOVE CERTIFICATE(S) ISSUED BY SUPPLY/TRADING HOUSE(S) WILL NOT BE ACCEPTED.

13. EVALUATION CRITERIA WILL BE FULL CONSIGNMENT WISE.

14. BIDDER(S) MUST ENSURE TO PROVIDE REQUIRED SPECIFICATION/INFORMATION/DOCUMENTS MENTIONED ABOVE. OGDCL CAN VERIFY ANY DOCUMENTS PROVIDED AND INCASE OF NON-VERIFICATION AND NON-PROVISION OF ANY REQUIRED DOCUMENTS BID(S) WILL BE REJECTED DURING TECHNICAL EVALUATION.

15. DELIVERY REQUIRED: - WITHIN TWO (02) MONTHS AFTER ESTABLISHMENT OF LETTER OF CREDIT C&F KARACHI BY SEA.

## SCHEDULE OF REQUIREMENT (SOR) DETAIL DESCRIPTION

SR #	DESCRIPTION	SPECIFICATIONS FOR MAST RAISING/LOWERING LINE (72 MM DIA), QUANTITY REQUIRED = 04 REELS	SPECIFICATIONS FOR DRAW WORKS/RIG FLOOR RAISING/LOWERING LINE (42 MM), QUANTITY REQUIRED = 04 REELS
1.	NOMINAL DIAMETER OF STEEL WIRE ROPE	72 mm	42mm
2.	LENGTH OF ROPE MEASURED FROM CENTRE LINE OF PINS ( OPEN X OPEN)	61.5 Meters	NA
3.	LENGTH OF ROPE MEASURED FROM CENTRE LINE OF PINS ( OPEN X CLOSE)	NA	40.5 Meters, Both Ends Solid thimble CH drilled to fit 72mm Pin.
4.	CONSTRUCTION	DF 8 8X36 Bristar OR EQUIVALENT.	DF8PI 8X36 OR EQUIVALENT.
5.	STRAND COSTRUCTION	36 (WS) (1-7-(7+7) +14)	36 (WS) (1-7-(7+7) +14)
6.	GRADE	1770 N/MM <sup>2</sup>	1960 N/MM <sup>2</sup>
7.	WIRE FINISH	GAL	GAL
8.	TYPE OF CORE	EPIWRC (BRISTAR)	EPIWRC
9.	LAY DIRECTION	RIGHT HAND REGULAR LAY	RIGHT HAND REGULAR LAY
10.	MINIMUM BREAKING FORCE	397.7 Tonnes	167 Tonnes
11.	LUBRICATION	Brilube OR EQUIVALENT	Brilube OR EQUIVALENT
12.	MASS/UNIT LENGTH IN KG/METER	EACH BIDDER TO SPECIFY OFFERED WIRE ROPE MASS IN KG PER METER.	EACH BIDDER TO SPECIFY OFFERED WIRE ROPE MASS IN KG PER METER.
13.	APPLIED STANDARD	API 9A/ISO	API 9A /ISO
14.	PACKING	EIPS ON WOODEN REEL	EIPS ON WOODEN REEL
15.	END FITTINGS (AS PER API RP 9B) ONE END	<i>CrosbyG416 Open Spelter Socket</i>	DIN 3091 Solid thimble
16.	END FITTINGS (AS PER API RP 9B) SECOND END.	<i>CrosbyG416 Open Spelter Socket</i>	DIN 3091 Solid thimble