

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT ISLAMABAD
FOREIGN SECTION

(To be completed, filled in, signed
and stamped by the principal)

ANNEXURE 'A'

Material PORTABLE MULTIGAS DETECTORS FOR NORTH FIELDS
Tender Enquiry No PROC-FE/CB/PE&FD-5059/2021
Due Date
Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY AIR	Total Price C & F BY AIR	Deviated From Tender Spec. If Any
1	PORTABLE MULTI GAS DETECTORS WITH ACCESSORIES AND OPERATIONAL SPARES. DETAIL SPECIFICATIONS ARE ATTACHED AT ANNEX-Z.	Number	15					

NOTE:

- 1. Bid Validity:** Bid must be **valid for 180 days** from the date of Technical Bid Opening
- 2. Bid Bond Amount:** USD 540/= (United States Dollar Five Hundred Forty only) or equivalent Pak Rupees **valid for 210 days** from the date of Technical Bid Opening. Bidders are advised to carefully read all clauses related to Bid Bond in Tender Document (Press-Single Stage Two Envelope) – Updated” available on OGDCL website
- 3. Evaluation Criteria:** - Full Consignment Wise By Air Islamabad
- 4. Delivery Period:** 02 Months from LC establishment
- 5.** Bidders are advised to carefully read all the terms and conditions of the Tender Document “Master Set of Foreign Tender Document (Press-Single Stage Two Envelope) – Updated” available on OGDCL website which is an integral part of this Schedule of Requirement

Annexure-Z

Portable Multi Gas Detector

Sr, No	Specifications	
1	Gas Detection	H2S, CO, O2, LEL
2	Flammable Gas (EX)	Measuring range (0-100% LEL)
3	Hydrogen Sulphide (H2S)	Measuring range 0-100ppm
4	Resolution	0.01ppm
5	Accuracy	(+_ 5%)
6	Sensor technology	Latest (IR or other)
7	Ingress Protection	IP66+
8	Intrinsically Safe	Yes
9	Charging Time	Less than 7 hours
10	Battery Option	Rechargeable Battery Pack
11	Working Time	Greater than or equal to 10 hours
12	Temperature	-2°C~50°C
13	Certifications and approval	Class I, Div. 1, Gr. A, B, C, D, ATEX/ IECEx , CE.
14	Alarm	Sound, light, vibration
15	Response Time	≤ 10S
16	Display	LCD with back light option
17	Vendors recommended Calibration kit comprising of regular tubing and cylinder	Yes (Bidder to quote price separately)
18	Accessories	Charger/Adapter, Concussion proof boot
19	Two year Operational Spares	One Set of replacement sensors