

Clarification No. 02

TENDER ENQUIRY NO. PROC-SERVICES/CB/P&P-5083/2021 **Hiring of services for installation of Filter Coalescer Vessel** **(FC-101) including fabrication, welding, cutting, installation,** **painting etc. of associated piping along with relevant E&I** **jobs at Qadirpur plant**

Some of the Prospective bidders have made a few queries against the subject Tender Enquiry. The queries along with OGDCL replies are given below for information of all the prospective bidders.

S.No	Clarification/Query	OGDCL REPLY
1	What are the Stress relieving requirements??As per code stress relieving starts from 19 mm Thick. In drawing pipe thickness is mentioned as 25.4 mm and stress relieving requirement is mentioned as "Not required". Please clarify whether we should follow provided drawings or code?	Code to be Followed, Stress relieving is required
2	In SOW RT is mentioned as 30 % of new weld joints whereas it is mentioned as 10 % in provided drawings. Please clarify whether the actual RT requirements is 30 % or 10 %?	30% RT to be performed, but RT of all 26" joints is mandatory
3	Paint specification as well as DFT are not mentioned. Please provide	Please find attached Paint Specification Doc
4	what is the maximum lifting height	Please find attached Lifting Doc