

Clarification No. 03

TENDER ENQUIRY NO. PROC-SERVICES/CB/P&P-5083/2021 **Hiring of services for installation of Filter Coalescer Vessel** **(FC-101) including fabrication, welding, cutting, installation,** **painting etc. of associated piping along with relevant E&I** **jobs at Qadirpur plant**

Some of the Prospective bidders have made a few queries against the subject Tender Enquiry. The queries along with OGDCL replies are given below for information of all the prospective bidders.

S.No	Clarification/Query	OGDCL REPLY
1	Refer to clause no 7 of contractor responsibilities, fabrication and installation of pipe supports, kindly share the total weight of pipe supports?	Plat form plus pipe supports = 2950 Kg Steel parts (Angle/MS plate/Anchors) embedded in civil foundation =450 Kg Bolts + Anchors = 190 Kg Total = 3590 Kg
2	Refer to clause no 10 of contractor responsibilities, regarding cement grout, kindly share the total Cubic meter of grout requirement for material estimation? Also share the skid sizes?	38.61 m2 Non Shrinkage cementitious gout (pipe supports, sleepers, platform) and (inlet/outlet, drain valve and filter coalescer)