

**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT, ISLAMABAD**  
**FOREIGN SECTION B**

(To be completed, filled in, signed and stamped by the principal)

**ANNEXURE 'A'**

**Material** PIPE REPAIR CLAMPS  
**Tender Enquiry No** PROC-FB/CB/PE&FD-5189/2021  
**Due Date**  
**Evaluation Criteria** FULL

**SCHEDULE OF REQUIREMENT**

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	PIPELINE REPAIR CLAMP, TYPE: SPLIT SLEEVE, FOR PIPELINE NPS 8", ANSI CLASS 600	Number	7					
2	PIPELINE REPAIR CLAMP, TYPE: SMITH PLUS/ PIN/ NEEDLE, FOR PIPELINE NPS 8", ANSI CLASS 600	Number	10					
3	PIPELINE REPAIR CLAMP, TYPE: SMITH PLUS/ PIN/ NEEDLE, FOR PIPELINE NPS 6", ANSI CLASS 600	Number	10					

- Note:**
- 1) BID VALIDITY: 180 DAYS FROM BID OPENING DATE.
  - 2) BID BOND: USD 590/- OR EQUIVALENT PKR TO BE SUBMITTED WITH BID AND VALID FOR 210 DAYS.
  - (3) DELIVERY PERIOD: 120 DAYS FROM L/C ESTABLISHMENT DATE.
  - (4) EVALUATION CRITERIA: "FULL CONSIGNMENT WISE" ON CFR BY SEA KARACHI-PAKISTAN BASIS.
  - (5) BIDDING PROCEDURE: SINGLE STAGE-SINGLE ENVELOPE.
  - (6) TENDER DOCUMENTS AVAILABLE ON OGDCL'S WEBSITE UNDER TAB "Tender Document for "Single Stage-One Envelope" Bidding Procedure:.

## TERMS AND CONDITIONS

Sr #	Description	Bidder's compliance
Bidder must meet following terms & conditions in order to technically qualify.		
1	Bidder must Comply SOR & Technical Specifications. (Signed & Stamped)	
2	<p>Bidder must quote the material from the manufacturer having manufacturing experience of min. 10 years. Bidder to provide the following information of the manufacturer.</p> <ul style="list-style-type: none"> <li>a- Company profile clearly mentioning the same type of goods for which bid is submitted.</li> <li>b- Establishment of company</li> <li>c- Manufacturing experience</li> <li>d- Sales record of last 10 years</li> <li>e- Website address:</li> <li>f- Postal address</li> </ul>	
2	Provision of authority letter from manufacturer in favor of bidder. (if bidder is not the manufacturer of the goods). Provision of authority letter from bidder in favor of local agent.	
3	<p>Bidder has to provide the supply record of bidder for the quoted material for the last 05 years in following format.</p> <ul style="list-style-type: none"> <li>a- Name of the company to whom material supplied</li> <li>b- Year of supply</li> <li>c- Type of material supplied mentioning sizes and pressure ratings</li> <li>d- Amount of the consignment</li> <li>e- E-mail and contact No. of the purchaser.</li> <li>f- Provision of copies of at least 05 Nos. of purchase orders from the last 05 years projects as per provided supply record.</li> </ul>	
4	<p>The manufacturer must have manufactured and supplied quoted material to international Oil &amp; Gas E &amp; P companies. International E &amp; P Companies should be upstream member of International Association of Oil &amp; Gas Producers (IOGP) or a member Pakistan Petroleum Exploration &amp; Production Companies Association (PPEPCA). Following documents to be provided along with the bid.</p> <ul style="list-style-type: none"> <li>a- Supply record.</li> <li>b- Provision of copies of at least 05 Nos. of purchase orders from the last 05 years projects.</li> <li>c- Bidder has to provide at least 03 Nos. performance certificates from the last customers to whom material supplied.</li> </ul>	
5	Bids of any manufacturer, whose material malfunctioned after installation against any previous contracts awarded by OGDCL, shall be rejected.	
6	All the material has to be compliant to NACE MR 0175. Bidder has to confirm that at the time of delivery, NACE MR 0175 certificate shall be provided for all the material. Bidder to confirm that NACE MR 0175 shall be embossed on sleeves.	

	manufacturer. a- ISO 9001:20008, b- ISO 140001:2004, c- BS-OHSAS 18001	
8	Bidder to provide the technical literature of manufacturer for the quoted material	
9	Bidder to confirm delivery period of 120 days after L/C Establishment C & F by sea Karachi.	
10	Bidder has to clearly mention the model of the clamps and provide its drawings in the bid.	
11	Bidder to confirm that all the material shall be brand new.	
12	Bidder to confirm that material shall be packed prior to shipment in accordance to international code and standard.	

## Technical Specifications

Sr. #	Description	Bidder's compliance
1	Size of Clamps must be according to <ol style="list-style-type: none"><li data-bbox="239 354 999 438">6-Inch NPS Line Pipe, Sch-40, ANSI Class 600, 3L-PE Coated.</li><li data-bbox="239 454 960 539">8-Inch NPS Line Pipe, Sch-40, ANSI Class 600, 3L-PE Coated.</li></ol>	
2	Inside diameters and lengths of the sleeves shall be designed as per requirement by the OEM.	
3	All the material grades for clamps body, studs/nuts, seals etc. shall be as per manufacturer recommendations.	
4	Ambient temperature varies from -5 to 50 Deg Celsius	
5	Temperature of the pipe line fluid shall be from 30-90 Deg. Celcius.	
6	Material of the line pipe shall be API 5L, X-52.	
7	Fluid within the line pipe shall be 3-phase fluid i.e. Oil, Gas and water.	
8	The material is required to be installed on uncle ground as well as above ground line pipe for repair.	