

Pre Bid Clarification-1, T.E PROC-FB/CB/PE&FD-5207/2021. Procurement of Jet Pump Wellhead Assemblies 2-9/16 inch 5000 PSI W.P. along with Accessories, Spares and Associated Services

Items	Reference	Clarification Question	OGDCL's Response
1.	General	Kindly advise if this is for Onshore or Offshore applications.	It is onshore requirement for Jet Pump Wells
2.	SOR Ring Gasket	Bidder offers RX gaskets instead of R gaskets, where applicable. RX gaskets are pressure energized, and more resistant to shock, vibration and thermal loading. RX gaskets can be used interchangeably with R ring grooves.	Acceptable
3.	SOR Stud Length	Bidder offers stud length per API 6A Annex I recommendation. Please confirm acceptance.	Acceptable
4.	SQR Control Lines	Please advise if control lines are required. Kindly advise the size & qty of control lines if applicable.	Not required in the SOR
5.	SOR Sr. #2.3 & 18 & 19	2" SCH 120 is not a standard size. Kindly advise the OD & ID required for the weld prep.	Bidders are required to Quote as per SOR
6.	SOR Sr. #7	Please confirm x-over material shall be L-80 Type 1, or L-80 13 Cr. Note that the Tubing Hanger body material will be 410 SS for EE-1.5.	Already mentioned in the SOR L-80 or Equivalent grade Type-1
7.	SOR Sr. #7	Kindly advise if x-over is required to be torqued up with Tubing Hanger (Sr. #6). Note that the qty of Sr. #6 is different from Sr. #7.	Serial-6, TPI criteria is mentioned at 16.v simple hand tight of Pin x Pin X-overs with tubing hangers threads to confirm the compatibility of Tubing hanger and X-overs threads Serial-7, Bidders are required to quote as per SOR
8.	SOR Sr. #13 Lubricator assembly 16 foot polished rod	Bidder offers our standard lubricator assembly with 144" (12 ft) stroke. Please confirm acceptance.	Bidders are required to Quote as per SOR
9.	SOR Sr. #14	Kindly confirm if the flanged body shall come with Fig 1502 female connection.	Pin connection Bidders are required to Quote as per SOR
10.	SOR Sr. #15	Kindly confirm if the flanged body shall come with Fig 1502 female connection.	Pin connection Bidders are required to Quote as per SOR
11.	SQR Figure 2	Please confirm that the 18" top and bottom length shown are for illustrative purposes only.	Bidders are required to Quote as per drawing