

PRE-BID CLARIFICATION#01
AGAINST T.E#PROC-FB/CB/PROD-4625/2020

This is with reference to subject tender enquiry and query received from prospective bidder, please be noted following clarifications:

Sr#	<u>Bidder Query:</u>	<u>OGDCL Reply:</u>
1	From the description and drawings of 77-83 items, we can only judge the type of channel of the gasket, but we don't know the type of gasket. We need you to tell us what kind of gasket they are, as there are many kinds of gasket, such as wound gasket, ring joint gasket, Serrated Gasket and so on.	The type of the gasket is mentioned in the description of the parts. These are Kammprofile AISI 304 + Graphite filled gaskets and are not wound/ring joint etc. These gaskets have a serrated metal (AISI-304) core with a soft facing material (graphite).
2	What type of corrosion protection method should be used for outer carbon steel ring of all wound gaskets? galvanized or painting? If painting, what color should be used?	In all spiral wound gasket corrosion protection i.e painting or galvanizing both are acceptable however galvanizing is preferred. Furthermore color coding shall be as per ASME B16.20.

NOTE: All other terms & conditions remain unchanged.