

CLARIFICATION#1 AGAINST TENDER # PROC-SERVICES/CB/P&P-4711/2020- HIRING OF SERVICES FOR EXECUTION OF ATA- Nashpa Plant

One of the potential bidder has asked following clarifications. OGDCL response is as under:-

Sr#	Questions for Clarification	OGDCL Reply
1	As per our understanding, the slug removing is not included in our scope. The sludge will be already removed before handing over to contractor. Please confirm.	Sludge Removal from CPI Tank (TR-3901) and Oily water Basin (T-3801), Minor Sludge from KO Vessels and separators to be disposed off by Contractor in designated area at Field.
2	Client is requested to please share the percentage of RT.	100% RT of all Butt welds. (scope of OGDCL)
3	Client is required to share the area for surface preparation job.	As per requirement of Third Party Inspection contractor.
4	Please mention that PQR and WPS is in client scope or contractor scope.	Contractor Scope
5	As per our understanding, any sort of direct material will be provided by client. Please acknowledge	Filters and gaskets will be OGDCL scope while consumables of welding will be contractor scope.