

**CLARIFICATION#1 AGAINST TENDER # PROC-SERVICES/CB/P&P-4875/2020- ATA QADIRPUR PLANT**

Following Clarification have been made in the subject tender.

S. No.	Query	OGDCL Reply
1	Please confirm that Refractory is in client scope or contractor scope. As mentioned in General terms and conditions, refractory material will be provided by OGDCL, so please confirm who will provide Installation services.	Refractory Material will be provided by OGDCL, whilst all related services will be provided by the contractor.
2	Please confirm that chemical cleaning is not required and if required then who will provide chemical.	SOW comprises of Fin Fan Type Coolers external cleaning only. Contractor will provide suitable cleaning agent/chemical.
3	Please confirm that PWHT is required or not.	PWHT will be required for Tie-In of FC-101 in FEC scope of work, Approx. Dia 338, Pipe Size: 26".
4	Please confirm who will provide water.	OGDCL.
5	Please confirm that idling due to client for switching train to other will not be contractor responsibility and idling will be charged.	ATA-2021 provided time duration will be final, no back charge will be admissible at any stage.
6	Please confirm RT percentage	Yes. Especially FC-101 Tie-In & other welding Jobs @ 30% of all welding Joints.
7	No special Requirement of Covid is required as per current scenarios.	All employees will wear Face mask, use Hand sanitiser, Maintain social distance & follow all SOP's related COVID-19 at the time of annual turn around.
8	All sort of Direct Material will be provided by client	Yes.
9	Lathe machine will be provided by client.	Lathe machines 10 ft length will be provided, availability depending upon Power limitations during ATA-2021.
10	No Flame arrestor is required for any equipment.	Flame arrestors are required for all vehicles, Diesel Welding machines etc.
11	Nitrogen for purging with pumping unit will be provided by client.	Yes.
12	No WQT for welders is required Valid card holders welders are acceptable to client	Welders must be qualified in last 3~6 months.
13	For Lapping, please confirm lapping machine will be provided by OGDCL or manual lapping will be done by contractor.	Lapping machine ball Butterfly valves (UV valves, 6" & 12", Qty: 40 No's approx) will be contractors

		responsibility.
14	Please confirm that material for valve seat will be provided by OGDCL	All material for reconditioning of valves (If any) will be contractors responsibility.
15	Valid card holders scaffolders and riggers are acceptable to client?	Yes.