

CLARIFICATION#1 AGAINST TENDER # PROC-SERVICES/CB/P&P-4940/2021- HIRING OF SERVICES FOR EXECUTION OF ATA-2021 JOBS AT UCH-II

Following clarifications have been made against subject mentioned tender:-

Sr#	Questions for Clarification	OGDCL Reply
1	Client is requested to Please share the BOQ's in excel.	BOQ/SOW Rev.01 uploaded on OGDCL website.
2	Please share your current covid-19 policy and any special requirements of Covid-19.	The general SOP laid down by GOP. However, OGDCL specific SOP/requirements will be shared to successful contractor after award of job.
3	As per Scope of work of UCH-II heat exchangers require chemical cleaning. Please specify the shell & tube fluid medium so we can propose the chemical material.	Fluid Medium of Shell & Tube of Heat Exchangers is given in SOW/BOQ Rev.01
4	Please confirm electricity and water for site works and hydro testing will be provided by client.	OGDCL will provide water & electricity
5	Client is requested to Please confirm the chemical material for chemical cleaning	3rd Party Chemical Cleaning expert company will confirm the chemical material as per service & metallurgy of Heat Exchangers
6	Client is requested to please confirm the percentage of refractory repair works.	Will be confirmed at the time of inspection
7	Below mentioned refractory material is required for refractory works as per ITB i. Fire Cement (25 Kg Bag) Qty: 10 Nos. ii. Castable (25 kg Bag) Qty: 30 Nos. So other than this material if required in actual than it will be provided by client Please confirm	Contractor have to arrange the material
8	All direct material including insulation will be provided by client. Please confirm	OGDCL will provide direct material excluding consumables
9	Client is requested to please share the scope/Quantity variance.	Currently all the provided SOW is needed to be covered however addition or deletion of SOW will remain within contract limit and it will not be more than 15% of total contract value.
10	Client is requested to please share the complete list of manual vales for overhauling scope.	List of manual valves is available in BOQ/SOW Rev.01
11	Please Specify the Shell material grade for chemical cleaning of Heat Exchangers.	Metallurgy of Shell & Tube of Heat Exchangers is given in SOW/BOQ Rev.01
12	Except DPT, Complete NDT including RT is in client scope. Please confirm.	Only DPT as per job scope requirement will be in the contractor scope
13	Please Confirm depth and height of Vessel pit that cleaning and decanting is required. Further Please share the slug	Given in BOQ/SOW

	material in PIT.	
14	Please confirm the quantum of PWHT.	As per ITB/SOW
15	Please confirm whether valid card holder welders are acceptable to OGDCL. If not, for welders qualification tests, test pieces & consumables will be provided by OGDCL. Kindly confirm.	3rd Party Valid Card Holder Welders are acceptable to OGDCL. In case of welder qualification test, OGDCL will provide test piece & consumable will be contractor responsibility
16	It is been considered as per previous practice that utilities like drinking water, washroom, instrument air, compressed air and other supplies will be provided by OGDCL. kindly confirm	Utilities will be provided as per previous practice. For ventilation, filters cleaning, any other requirement Contractor will have to arrange air compressors accordingly
17	Any 3rd party requirement for PSVs. Please confirm	There is not PSV's included in revised SOW Rev.01
18	As per our understanding nitrogen purging is in OGDCL scope. Contractor will only assist in nitrogen purging. Kindly confirm.	YES
19	Kindly confirm is there any modification job in contractor's scope. As there is no such thing mentioned in tender document.	As per ITB/SOW, please refer Group-E
20	Valid card holders scaffolders and riggers are acceptable to client?	3rd Party Valid Card Holder Scaffolders & Riggers will be acceptable to OGDCL
21	As per ITB, respirator is required, please share its specification and requirements.	It is the safety requirement of contractor as per HSE international standards for Oil & Gas Industry
22	Please confirm that material for valve seat will be provided by OGDCL	OGDCL will provide material for valve seat
23	Please confirm that removed sludge material will be disposed in the plant or outside the plant. If outside plant then confirm distance. Further for transportation of slug, bowser will be provided by Client or Contractor.	Slug/waste will be disposed off outside the plant and it will be the responsibility of contractor
24	Please confirm that sand blasting is required for piping job and who will provide sand for sand blasting.	There is not any requirement of sand blasting for piping jobs.