

CLARIFICATION NO. 3

**CLARIFICATION NO.3 AGAINST TENDER ENQUIRY NO. PROC-SERVICES/CB/CORR-2029/2017 FOR
HIRING OF CP SYSTEM INSTALLATION AND COMMISSIONING**

Some of the prospective bidders have raised some queries against the subject Tender Enquiry. The replies of the same are given below for information of all prospective bidders:

S.No	Query	OGDCL Response
1	No of Anodes at Solar /TEG systems.	<ul style="list-style-type: none">• Number of anodes for all three types of power systems i.e TEGs, Solar Units, and TR Units shall be 5 - 10.• Type of anode beds shall be shallow.• One AJB shall be required for each system. However number of test posts shall vary from 2 - 8 depending upon actual situation.• Cable trenches specs shall be as per code and field requirement.• Length of cable shall be as per actual field / CPS requirement
2	Type of Anode bed at TEG system (deep well or shall)	
3	Depth of bore and Dia of bore for TEG system Anode ground bed	
4	No of Anodes at TR systems.	
5	Type of Anode bed at TR system (deep well or shall)	
6	Depth of bore and Dia of bore for TR system Anode ground bed	
6	No of AJBs and Test posts per system.	
7	Cable Trenches specs I.e. depth and width	
8	Length of cable excavations per system.	
	OGDCL coke pumping procedure if any.	