



NASHPA COMPRESSION FACILITY PROJECT



Tender Enquiry No.: PROC/FC/CB/PROJ/NASHPA-3268/2018

PRE-BID CLARIFICATION # 06

One of the bidder has asked following queries, OGDCL/ENAR responses are as follows:

| Sr. No. | Clarification By Bidder | OGDCL / ENAR Response |
|---------|--|---|
| 1 | <p>Section (with Page No): SEC-III, Scope of work, Page 4 Clause 1.1.2.</p> <p>Subject: EPCC Contractor shall provide proper double block & bleed and positive isolation for all process piping tie-ins.</p> <p>Question: In scope of work, EPCC contractor shall provide Double Block & Bleed and positive isolation for all process piping tie-in, but in P&ID, DBB valve isn't at the process piping tie-in. Do the tie-ins with instrument element and SC shall provide DBB valve? Does the DBB valve have some special requirement or according to the NGP-000-PIP-15.03-0001-00-02-Piping Material Specification is OK?</p> | <p>For tie-ins and isolation of equipment & instruments etc, refer P&IDs, which shall be further reviewed and confirmed during Detail Engineering.</p> |
| 2 | <p>Section (with Page No): SEC-III, Scope of work,</p> <p>Subject: NGP-000-SCW-15.01-2005-23-02-Site Grading and Leveling Plan.pdf</p> <p>Question: Clarification for Civil work Please verify demolishing the existing raw water pond is in the scope of work.</p> | <p>The Project area would be cleared by OGDCL for any other installation, as already mentioned in para No. 5 of clause 12.3.12 "Civil and Structural Work" of Scope of work.</p> |
| 3 | <p>Section (with Page No): SEC-III, Scope of work,</p> <p>Subject: NGP-000-GEN-15.01-0001-00-02-General Plot Plan 0193-PC-001 (PLOTPLAN FOR FEC AREA)</p> <p>Question: Clarification for Civil work According to the table of minimum equipment spacing (NGP-000-GEN-15.03-0001-00-00), the distance between pipe rack and compressor shall be 15m (and the distance is 8m in the drawing). Please confirm the contractor's understanding is correct.</p> | <p>Minimum equipment spacing as per OGRA standard with respect to the Compressor & pipe rack has been considered which is 8 meter. Bidder to ensure the minimum spacing as per OGRA standard.</p> |