PRE-BID CLARIFICATION NO. 7

<u>COMPANY'S RESPONSE TO BIDDERS' CLARIFICATIONS ON TENDER DOCUMENT FOR</u> HIRING THE SERVICES OF PCC CONTRACTOR FOR SUPPLY / INSTALLATION / CIVIL FOUNDATIONS FOR MISCELLANEOUS EQUIPMENTS & PLANT BUILDING WORKS FOR MELA DEVELOPMENT PROJECT (PCC)

(TENDER ENQUIRY NO. PROC-FC/CB/PROJ/MELA-3368/2018)

Sr. No.	BIDDERS' QUERY	REFERENCE	COMPANY REPLY / CLARIFICATION
1.	Refer to ITB Vol-1, page 163 / 653, item # 13, CP for UG Piping, please confirm if the sacrificial anodes for UG piping are for temporary protection? Usually it is done on temporary basis for plant piping till the permanent system is energized. Please clarify.		Sacrificial anode based CP for UG piping shall be considered for permanent protection.
2.	Refer to the ITB Vol-1, page 45 / 653, OGDCL shall make progressive payments to PCC Contractor on monthly basis against verified percentage completion of work however refer to Annexure – XIII, page 86 / 653, Mechanism of progress payment, please confirm that payment to contractor shall be made based on work completion % age verified by client engineer and not 100% completion of work activities.		 Refer ITB Vol-1, page 45 / 653, it is very clearly written for Works (Covering Construction, Installation & Erection, Pre- Commissioning, Commissioning & Start-up that: "OGDCL shall make progressive payments to PCC Contractor on monthly basis against Contractor's invoices giving details of that specific work and its completion status. The payment shall be made considering the Bid Price Schedule and verified percentage completion of work. The measurement/verification mechanism for progressive payments is detailed in Annexure-XIII. The measurement/verification of work will be made by OGDCL/Consultant based on progress reports submitted by the Consultant and actual at site." It is very clear from above that payment to contractor shall be made based on work completion % age verified by Client / Consultant at site.
3.	Refer to the BOQ there is no line item for mob demob cost, please clarify.		Mobilization Advance and its details are well defined in Tender Document.

Sr. No.	BIDDERS' QUERY	REFERENCE	COMPANY REPLY / CLARIFICATION
4.	Refer to the mechanical BOQ Item # 10.1 & 11.0, please confirm that which BOQ covers the civil foundation quantities for transfer pump and filling pump.		Quantities of the pump foundations are included in the BOQ of sheds, refer 165-2-BQC-002 (sheet 3 of 8)
5.	Refer to ITB Vol-2, page 51 / 1625, item # 3.5, clause o, Instrument air shed, however there is no BOQ line items for the supply and installation of instrument air shed. Please clarify.		Instrument air shed had been renamed as Utility Shed, its quantities are provided in the BOQ.
6.	Further we are not able to download the clarification 6 to 8 from the OGDCL website. The message appear as (File does not exist). Please email the same.		This is clarification no.7. OGDCL will re-upload the Clarification no.6 on its website.