

PRE-BID CLARIFICATION NO. 10

**COMPANY'S RESPONSE TO BIDDERS' CLARIFICATIONS ON TENDER DOCUMENT FOR
HIRING THE SERVICES OF PCC CONTRACTOR FOR SUPPLY / INSTALLATION / CIVIL FOUNDATIONS FOR
MISCELLANEOUS EQUIPMENTS & PLANT BUILDING WORKS FOR MELA DEVELOPMENT PROJECT (PCC)
(TENDER ENQUIRY NO. PROC-FC/CB/PROJ/MELA-3368/2018)**

Sr. No.	BIDDERS' QUERY	REFERENCE	COMPANY REPLY / CLARIFICATION
	GENERAL		
1.	Our understanding about the referred paragraph is that it is not applicable to PCC contractor and we are only responsible to quote against the information provided in respective BOQs	165-2-SPG-130, Rev 0, Page # 6 of 89 (Scope of work S.No.3 Para 2)	This is part of Tender Document and SOW and to be considered as Contractor's obligations. Variations from or additions to the Tender shall be called to the attention of the Company for review and approval.
	MECHANICAL AND PIPING WORKS		
1.	a) In referred Piping BOQ, we understand that it covers the scope of (I) interconnecting piping, (II) Pipe rack piping, (III) Equipment to equipment piping, (Iv) Tie-in etc. Please confirm our understanding. b) In piping BOQ, no Insulation BOQ is given and we understand no insulation is required.	BOQ # 165-2-BQM-002, Rev. 0 (Piping)	Bidder's understanding is correct.
2.	Item no. 1.2 of referred BOQ, equipment weight is not given kindly provide the breakup of equipment along with weight.	BOQ # 165-2-BQM-001, Rev. 1 (Mechanical)	Refer vendor data for instrument air system attached in tender document (Volume-II).

Sr. No.	BIDDERS' QUERY	REFERENCE	COMPANY REPLY / CLARIFICATION
3.	Item.# 4.5 of referred BOQ Foam pourer/Chamber, for modification in 08 nos condensate storage tanks as per API - 653, we need detail of modification , Kindly provide the detail.	BOQ # 165-2-BQM-001, Rev. 1 (Mechanical)	<p>Quantities for Foam Pourer Assembly shall be estimated by contractor as per scope mentioned in tender documents.</p> <p>References of Tank Drawings, Datasheets are provided in the 165-2-BQM-001, Rev.1 for reference and are also attached in Tender Document.</p> <p>Same has already been communicated in Pre-Bid Clarification no. 8.</p> <p>Bidders are requested to read the tender and clarifications carefully prior to putting clarifications.</p> <p>Furthermore, Contractor to submit procedure for installation & testing for approval from owner along with the bid documents.</p>
ELECTRICAL AND INSTRUMENTATION WORKS			
1.	Kindly provide document refer to FAS (165-2-SPE-022) to support resource estimation	165-2-BQE-004 item # 8 (Fire Alarm System)	Please refer Point # 3 of Pre-Bid Clarification 2.
2.	As per the BOQ description, ADDRESSABLE FIRE ALARM CONTROL PANEL(S) MINIMUM OF TWO LOOPS WITH ANY COMMUNICATION MODULES REQUIRED TO INTERFACE / INTEGRATE MULTIPLE FACPS. COMPLETE SYSTEM INTEGRATION. Please advise if integration is required between the new FACP and any existing FACPs. If requirement is the same, then we need to know the existing FACP details and type of interface. We understand that location of FACP is required in new MCC room?		Please refer Point # 3 of Pre-Bid Clarification 2. The integration of new FACP with existing and location of new FACP will be tackled during detail design/construction stages and the data of existing FACP will be shared after award to the successful bidder.
3.	Refer pre -bid clarification # 7, we understand that the permanent cathodic protection is required for complete underground piping mentioned in BOQ # 165-BQM-002, Attach-2A, S.No.2 under the heading POLYETHYLENE TAPE WRAP COATING, the total length of which is 4896 meters (Including all dia. pipes). Kindly confirm	165-2-BQE-005 S.No.13 (Cathodic Protection)	CP is not required for underground polyethylene tape wrap coated piping.
4.	We understand that Flood lights for these poles are covered in S.No. 3 & 4 of the referred BoQ (Hazardous and Non hazardous flood lights) Kindly confirm	165-2-BQE-002 S.No.5 (Lighting Poles)	Bidder's understanding is correct.

Sr. No.	BIDDERS' QUERY	REFERENCE	COMPANY REPLY / CLARIFICATION
5.	<p>We are facing some delays from equipment manufacturers to acquire quotations from Europe due to the ongoing summer holidays.</p> <p>Therefore, it is kindly requested to extend the bid submission date for the project for 4 weeks (6th August to 3rd September 2018). This will enable us to prepare a comprehensive and competitive proposal as per actual scenarios.</p>	<p>DEL/PCOGDCL/MELA /004 (Extension in Bid Submission Date)</p>	<p>There is no bid extension at present; OGDCL will publish bid extension dates on its website, if any.</p>