PROCUREMENT (SUPPLY), CONSTRUCTION, INSTALLATION/ERECTION, PRE-COMMISSIONING, & COMMISSIONING ASSISTANCE FOR NEW CENTRIFUGAL COMPRESSORS AND MODIFICATION WORKS OF EXISTING TURBO COMPRESSOR TRAINS FOR QADIRPUR COMPRESSION PROJECT

TENDER ENQUIRY NO. PROC-FC/CB/PROJ/QP-4369/2019 POST-BID CLARIFICATION No. OGDCL-QP-4369-016



Sr. No.	Bidder Query	OGDCL/ENAR Response (31-Oct-2019)
1	Kindly confirm execution window of project	The tentative schedule for PC Contractor mobilization is just after compeletion of Commercial evaluation of this tender i.e. within next three to forth months. However, Bidder to confirm the bid validity as per Tender requirements.
2	Kindly confirm backfilling material for cable trench will be reused excavated material or fine sand will be used for back filling?	Please refer typical details for cable trench 0220-ELF-6801 SH 11 OF 11, where the requirement/use of fine sand and excavated soil with minimum dimensions are mentioned. Further, please note that as the plant is existing, therefore, excavation on proposed cable trench route shall be done manually. Bidder to consider accordingly.
3	Kindly share sand bedding size and thickness of sand layer.	Please refer typical details for cable trench 0220-ELF-6801 SH 11 OF 11 for the required details.
4	For new cable sleeves road width is required for road cutting.	Road width is 6meter wide. Please refer plot plan also.
5	Road cutting is required or Thrust boring will be preferred?	Bidder to follow respective BOQ details, notes and specification of the tender for such details.
6	For road Patching asphalt wiring is required or concrete filling will be used for road patching.	Bidder to follow respective BOQ details, notes and specification of the tender for such details.
7	Dimension of drawings are not given kindly share drawings with dimension.	Please clarify/mention the drawings nos.
8	Kindly share technical spacification of Heat tracing for designing process.	Heat tracing is not required.
9	Kindly share lay out of underground piping for designing of Cathodic Protection System.	For CP desing Bidder to consider tender BOQ and pre-bid clarifiations already provided on web.

PROCUREMENT (SUPPLY), CONSTRUCTION, INSTALLATION/ERECTION, PRE-COMMISSIONING, & COMMISSIONING ASSISTANCE FOR NEW CENTRIFUGAL COMPRESSORS AND MODIFICATION WORKS OF EXISTING TURBO COMPRESSOR TRAINS FOR QADIRPUR COMPRESSION PROJECT

TENDER ENQUIRY NO. PROC-FC/CB/PROJ/QP-4369/2019 POST-BID CLARIFICATION No. OGDCL-QP-4369-016



Sr. No.	Bidder Query	OGDCL/ENAR Response (31-Oct-2019)	
10	Kindly share Cable schedule of installed cables for cable dismantling job.	Cable sizes are mentioned in respective BOQs (Doc. No. 0220-GA-8001-05, PS-502, Sr.01). For lighting and earthing cable estimation, please refer respective layouts.	