

PROCUREMENT (SUPPLY), CONSTRUCTION, INSTALLATION/ERECTION, PRE-COMMISSIONING, & COMMISSIONING ASSISTANCE FOR NEW CENTRIFUGAL COMPRESSORS AND MODIFICATION WORKS OF EXISTING TURBO COMPRESSOR TRAINS FOR QADIRPUR COMPRESSION PROJECT

TENDER ENQUIRY NO. PROC-FC/CB/PROJ/QP-4369/2019

POST-BID CLARIFICATION No. OGDCL-QP-4369-019



Sr. No.	Bidder Query	OGDCL/ENAR Response (08-Nov-2019)
Electrical		
1	Reference to Supply of Electrical BOQ PS 403 Line Item 1 Shows that bidder shall provide grounding Rod Pits etc but Typical drawing 220-ELF-6801 shows 50x6mm Strips instead of Copper Rod. Also Depth of Grounding Pit not mentioned in Typical drawing.	Bidder to consider grounding rod pits. Revised Typical drawing 220-ELF-6801 is attached for reference.
2	Reference to Electrical BOQ PS 506 CP system please provide the Isometric drawings for design calculations.	<p>Please refer Spec. No.0220-GA-8001, section NO. 3.17.1 for the scope for cathodic protection system. The detailed design for cathodic protection is in Bidder's scope. Further, please note that Design and installation of CP System shall be carried out through NACE CP Technologist or / I-Corr Certified having at least 10 years' of relevant experience.</p> <p>Please refer Mechanical BOQ 0220-GA-8001B-03, PS - 310B for piping size and quantity.</p>