

PROCUREMENT (SUPPLY), CONSTRUCTION, INSTALLATION/ERECTION, PRE-COMMISSIONING, & COMMISSIONING ASSISTANCE FOR NEW CENTRIFUGAL COMPRESSORS AND MODIFICATION WORKS OF EXISTING TURBO COMPRESSOR TRAINS FOR QADIRPUR COMPRESSION PROJECT

TENDER ENQUIRY NO. PROC-FC/CB/PROJ/QP-4369/2019

POST-BID CLARIFICATION No. OGDCL-QP-4369-021



Sr. No.	Bidder Query	OGDCL/ENAR Response (08-Nov-2019)
Electrical		
1	<p>BOQ for Electrical Heat Tracing System Query: In bid document 0220-GA-8001-2 scope of work Class 1 mentioned Design, supply, installation, testing and commissioning of Electrical Heat Tracing System and NO.3.17.1 also mentioned refer to BOQS, pls provide BOQS.</p>	Heat tracing is not required.
2	<p>Primary System Diagram & Electrical Load and Breaker List Query:In Schedule-A document 0220-GA-8001-04 PS-401 about MCC ,please provide the Primary System Diagram & Electrical Load and Breaker List</p>	Please refer single line diagram Dwg no. 0220-ELB-6600 & 0106-ELB-6601 for the required details. Electrical load list is also attached with tender (Refer doc# 0220-ELA-6506).
3	<p>Clarify the meaning of BTD Query: In Schedule-A document 0220-GA-8001-04 PS-401 mentioned "The supply shall also include type tested BTDs (02nos) having IP54 rated minimum". Please clarify the meaning of BTD device.</p>	BTD means for Bus tie duct. Please refer single line diagram Dwg no. 0220-ELB-6600 & 0106-ELB-6601 and MCC Room Equipment layout (0106-ELD-6705-3) carefully, where scope is defined clearly that new switchgear/MCC panels SB-01A, B and C shall be extended through BTD or dummy panel as illustrated.