

PROCUREMENT (SUPPLY), CONSTRUCTION, INSTALLATION/ERECTION, PRE-COMMISSIONING, & COMMISSIONING ASSISTANCE FOR NEW CENTRIFUGAL COMPRESSORS AND MODIFICATION WORKS OF EXISTING TURBO COMPRESSOR TRAINS FOR QADIRPUR COMPRESSION PROJECT

TENDER ENQUIRY NO. PROC-FC/CB/PROJ/QP-4369/2019

POST-BID CLARIFICATION No. OGDCL-QP-4369-010



Sr. No.	Bidder Query	OGDCL/ENAR Response (24-Oct-2019)
1	In Dismantling Earthing material, do we have to take out the earthing conductors buried in concrete slab or just isolate the earth above ground.	Earthing pits/conductors shall not be dismantled buried in concrete slab. However, if any civil or mechanical support / foundation obstructs due to expansion of existing foundations / supports as per new interstage / afterstage coolers & compressors placement, in this case Contractor's scope shall also include the dismantling of required earth pits/conductor and will relocate the same to re-instate the earth network to achieve the required earth resistivity.
2	In heat tracing drawings package , Drawing no 022-ELA-6507 is missing, kindly provide the referred drawing.	Heat tracing system is not required.