

**PROCUREMENT (SUPPLY), CONSTRUCTION, INSTALLATION/ERECTION, PRE-COMMISSIONING, & COMMISSIONING ASSISTANCE FOR NEW CENTRIFUGAL COMPRESSORS AND MODIFICATION WORKS OF EXISTING TURBO COMPRESSOR TRAINS FOR QADIRPUR COMPRESSION PROJECT**

**TENDER ENQUIRY NO. PROC-FC/CB/PROJ/QP-4369/2019**

**POST-BID CLARIFICATION No. OGDCL-QP-4369-015**



Sr. No.	Bidder Query	OGDCL/ENAR Response (28-Oct-2019)
1	Reference to Electrical BOQ 220-GA-8001-05 PS 506 Line Item 4 "Cathodic Protection System "we are requiring detail documents i.e. Isometrics, Detail specifications total length of pipeline where CP system required.	<p>Please refer Spec. No.0220-GA-8001, section NO. 3.17.1 for the scope for cathodic protection system. The detailed design for cathodic protection is in Bidder's scope. Further, please note that Design and installation of CP System shall be carried out through NACE CP Technologist or / I-Corr Certified having at least 10 years' of relevant experience.</p> <p>Please refer Mechanical BOQ 0220-GA-8001B-03, PS - 310B for piping size and quantity.</p>
2	Please provide us Existing Switchgears Manufacturer name, where need to couple new switchgears.	Existing Panel brand is LG Industrial system.