

Clarification

PROC-FB/CB/DRLG/D-4801/2020

Point wise reply to the Clarifications in BOLD RED letters is as under;

1. Kindly confirm that - Group B: 18 5/8" item is required with 17.000in special drift as it has been awarded and supplied before. Please note special drift of 17.500in on this dimension (139ppf) is likely to be a typo as the nominal ID=17.185in making drift physically unachievable. **OGDCL REPLY: INCONVENIENCE IS REGRETTED PLEASE, IT IS TYPO ERROR. REQUIRED DRIFT FOR 18-5/8" CASING IS 17" INSTEAD OF 17.5".**
2. Kindly confirm all premium threaded and coupled connections (Groups A, B, C, D, E & F) must equal or exceed pipe body ratings in Tension, compression, burst and collapse in accordance with clause 6. **OGDCL REPLY: YES**
3. Kindly confirm PSL-3 certifications requirements for 10 years despite the quoted item. **OGDCL REPLY: YES, THE QUOTED MANUFACTURING MILL/MILLS AGAINST ANY ITEM OR GROUP OF CASING MUST HAVE CONSECUTIVE (WITHOUT BREAKS) API 5CT, PSL-3 CERTIFICATION FROM JANUARY 2010.**