

Clarification No. 02

TENDER ENQUIRY # PROC-SERVICES/CB/DO-4817/2020

HIRING OF CASING RUNNING SERVICES

One of the Prospective bidders has made a query against the subject Tender Enquiry. The query along with OGDCL replies is given below for information of all the prospective bidders.

S.N.	CONTRACTOR'S CLARIFICATION	OGDCL Reply
01	Please advise when equipment and crew standby charges will apply / start.	Already mentioned in clause V GENERAL in OGDCL TOR that "Stand by rate will be applicable after arrival of equipment & crew members at OGDCL well site and will cease after release of equipment & personnel from the well site".
02	Please advise if Jam operators / engineer will be included in the mentioned 04 personnel or should be given separately.	Already mentioned in clause II PERSONNEL that Maximum 04 Crew members consisting one supervisor and three operators are allowed at well site for any Casing job". Therefore, any other essential crew will be included in the aforementioned personnel.
03	Please confirm if Jam unit (for premium connections) charges will be in the package or should be given separately.	Bidder be noted that all the charges will be in the package rate (Lump sum) operating cost/day. No separate charges for any equipment will be applicable.
04	Please advise Casing cutter will be in package or should be given separately.	Bidder be noted that all the charges will be in the package rate (Lump sum) operating cost/day. No separate charges for any equipment will be applicable.
05	Please advise circulating head requirement. It will be in package or should be given separately.	Bidder be noted that all the charges will be in the package rate (Lump sum) operating cost/day. No separate charges for any equipment will be applicable.
06	Please advise Bails requirement. It will be in package or should be given separately.	Bidder be noted that all the charges will be in the package rate (Lump sum) operating cost/day. No separate charges for any equipment will be applicable.
07	Please advise Bucking Frame requirement. It will be in package or should be given separately.	Bidder be noted that all the charges will be in the package rate (Lump sum) operating cost/day. No separate charges for any equipment will be applicable.
08	Please advise Spider & Elevator will be in package or should be given separately.	Bidder be noted that all the charges will be in the package rate (Lump sum) operating cost/day. No separate charges for any equipment will be applicable.

S.N.	CONTRACTOR'S CLARIFICATION	OGDCL Reply																											
09	Depth to run each size of Casing is not defined. Please clarify.	<table border="1" data-bbox="1192 185 1927 553"> <thead> <tr> <th data-bbox="1201 191 1436 224">Hole Section</th> <th data-bbox="1442 191 1682 224">North Region (M)</th> <th data-bbox="1688 191 1919 224">South/Centre (M)</th> </tr> </thead> <tbody> <tr> <td data-bbox="1201 228 1436 261">24-1/2"</td> <td data-bbox="1442 228 1682 261">0 to ± 400</td> <td data-bbox="1688 228 1919 261">0 to ±300</td> </tr> <tr> <td data-bbox="1201 266 1436 298">20"</td> <td data-bbox="1442 266 1682 298">0 to ±500</td> <td data-bbox="1688 266 1919 298">0 to ±400</td> </tr> <tr> <td data-bbox="1201 303 1436 336">18-5/8"</td> <td data-bbox="1442 303 1682 336">0 to ±500</td> <td data-bbox="1688 303 1919 336">0 to ±1400</td> </tr> <tr> <td data-bbox="1201 341 1436 373">14"/ 13-3/8"</td> <td data-bbox="1442 341 1682 373">0 to ±3000</td> <td data-bbox="1688 341 1919 373">0 to ±2000</td> </tr> <tr> <td data-bbox="1201 378 1436 410">9-7/8"/ 9-5/8"</td> <td data-bbox="1442 378 1682 410">0 to ±4500</td> <td data-bbox="1688 378 1919 410">0 to ±3000</td> </tr> <tr> <td data-bbox="1201 415 1436 448">7"</td> <td data-bbox="1442 415 1682 448">0 to ±5000</td> <td data-bbox="1688 415 1919 448">0 to ±3500</td> </tr> <tr> <td data-bbox="1201 453 1436 485">5"</td> <td data-bbox="1442 453 1682 485">0 to ±6000</td> <td data-bbox="1688 453 1919 485">0 to ±4000</td> </tr> <tr> <td colspan="3" data-bbox="1201 490 1919 548">Note:- Sections TD is tentative and It may vary as per actual well plan and is different for different wells.</td> </tr> </tbody> </table>	Hole Section	North Region (M)	South/Centre (M)	24-1/2"	0 to ± 400	0 to ±300	20"	0 to ±500	0 to ±400	18-5/8"	0 to ±500	0 to ±1400	14"/ 13-3/8"	0 to ±3000	0 to ±2000	9-7/8"/ 9-5/8"	0 to ±4500	0 to ±3000	7"	0 to ±5000	0 to ±3500	5"	0 to ±6000	0 to ±4000	Note:- Sections TD is tentative and It may vary as per actual well plan and is different for different wells.		
Hole Section	North Region (M)	South/Centre (M)																											
24-1/2"	0 to ± 400	0 to ±300																											
20"	0 to ±500	0 to ±400																											
18-5/8"	0 to ±500	0 to ±1400																											
14"/ 13-3/8"	0 to ±3000	0 to ±2000																											
9-7/8"/ 9-5/8"	0 to ±4500	0 to ±3000																											
7"	0 to ±5000	0 to ±3500																											
5"	0 to ±6000	0 to ±4000																											
Note:- Sections TD is tentative and It may vary as per actual well plan and is different for different wells.																													
10	As per point 2 of Scope of Work; Top Drive casing running services are required for North Region, South/Centre Region. Please confirm if OGDCL anticipates Top Drive services for ALL casing sizes, i.e. 20" thru 9-5/8".	Already mentioned in Rate format & Financial Evaluation Criteria of OGDCL TOR.																											
11	As per point III of Clause 1, General; "Backup Tools will be included for each Casing Size at no additional cost/charges". Please confirm that OGDCL expects backup Top Drive unit to be provided at location at no extra cost/charge.	No rental charges are applicable for any back up tools including top drive for each Casing Size for all groups at no additional cost/charges as per OGDCL TOR.																											
12	As per point III of Clause 1, General; Essential tools list is not provided for any size of casing package. Please clarify.	Essential tools/items will be included in package rate (Lump sum) operating cost/day for each Casing size. No additional cost/charges will be payable to contractor as per OGDCL TOR.																											
13	As per point III of Clause 2, Equipment; The requirement / quantities for Dope and thread locking compound is not mentioned for each size of casing.	As per actual consumption during casing running job.																											
14	As per point V of Clause 2, Equipment; Casing Cutter requirement along with Operator should be part of its job. However, the cost of operator is not covered in the tender document. Please Clarify. Also please clarify if Mobilization / Demobilization of casing cutter is required.	The cost of cold casing cutting is included in the package rate. However, if the operator for cold casing cutter is required separately by OGDCL then the charges quoted by the bidder for casing crew and mob/demob for said casing size in rate format will be applicable.																											
15	As per point VI of Clause 2, Equipment; The spider elevator and spider slip capacities are always in accordance with the depth of the casing to be run, in this case the depths for each casing sizes is not given hence it would be difficult to identify the capacity required.	Please refer the OGDCL reply at S.No#01, tentative/expected depth of each casing is provided.																											
16	As per Rate Format; In all sizes of casings, OGDCL has asked for 4 personnel. Note that actual requirement could be up to 7 persons in case the casing is run more than 1,000 meters, with JAM units. As per QHSE standards the one shift is not more than 6 Hours for casing crew.	OGDCL requirement of 04 no's casing crew retains same, which is as per TOR.																											
17	They need to understand the number of CRT required for running these sections, if in case of a mixed string due to the difference in wellhead allocations or other well design factors.	Normally a mixed string is not used in OGDCL as yet, if in case of a mixed string due to any reason, charges of CRT equipment separately will be applicable.																											