## **CLARIFICATIONS**

## PROC-FE/CB/ML-4841/2020 Mud Logging Units

Query	Clarification
DNV-CN 2.7-1 & 2.7-2. The correct terminology should be DNV GL 2.7-1 & 2.7-2, please clarify.	Actual term of certification is DNV 2.7-1 and no matter of any organization term GL or CN.
DNV 2.7-1 and 2.7-2 is for Cabinet (Container), So the Certification is applicable on Container Manufacturer. Please confirm.	Yes, DNV 2.7-1 and 2.7-2 is for container certification by manufacturer.
DNV2.7-2 is for offshore; please kindly confirm the end use?	It's up to you either you provide DNV 2.7-1 or 2.7-2 but must be use of zone-1 area, onshore harsh environment and pressurized unit.
Please Note DNV 2.7-1 and 2.7-2. Is not a standard certificate like ISO or API. It is an inspection report for each container with Serials Number, case by case. If you want this certificate for this cargo, we can only supply after award of contract. During the tender process, we can only share history certificates for reference.	The standard certification is concerned with all types i.e. structural welding code, cabin steel wall thickness, protected with fire resistant, lifting rings, lifting slings and meet the requirement of offshore movements.
There's no information about dimension of mud logging cabin. Please advise.	Dimension of Mud Logging cabin must be as per industry standard.

Syed Hassan Abbas Munager (Mud Logging) Ph: 051-9259139