

CLARIFICATION

TENDER ENQUIRY NO. PROC-FE/CB/ML-4841/2020

MUD LOGGING UNITS

Query. 1.2#DNV 2.7-2 is for Electronic standard of offshore activity. We think it is not necessary to have DNV2.7-2 standard mudlogging unit which works in Pakistan. Please kindly confirm if it will be used in offshore. Anyway, we can supply DNV2.7-2 mudlogging unit, it will cause the price increase dramatically, and DNV inspection will affect the delivery time.

Reply: As concern with Mud Logging Cabin it should be A0 rated material for Zone1 and DNV2.7-1 & DNV2.7-2 both certification is mandatory as per TOR.

Query.1.2#Please confirm the size of such mudlogging unit (Cabin), normally it should be 24ft, 27ft.etc, without certain size, we cannot quote accurate price.

Reply: Normally, Industry standard size is equal or above L=27ft, W=8ft H=9ft, less then this dimension is not acceptable.

Query.8.3# Environment gas detection system with sensors, please clear with more details.

Reply: Gas detector to detect Toxic gases (Poisonous by inhalation) and combustible from environment.

Query. Delivery period: 90 days from establishment of LC.DNV 2.7-2 certification cost 60+ days, so 90 days for delivery is not enough.

Reply: DNV certification and delivery of consignment is a bidder responsibility to parallel route accordingly.


Syed Hassan Abbas
Manager (Mud Logging)
Ph: 051-9259139