

TENDER CLARIFICATIONS

Customer :	OGDAL	Clarification No :	TC 01
Tender No :	Email request	Date :	03-MAR-2021
Description :	Wellhead Assembly and Accessories	Our Reference No :	SG-0000248-R00

Reference to the above bid invitation; we seek your clarifications on the following and appreciate your response by/ before 5th March 2021.

Thank you.

Items	Clarification Question	Customer's Response
Group B – Section A Item 1.14 – Stud 2” x 17.75”	Bidder will like to propose the stud length per API 6A which is 17.500”. Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group B – Section C Item 3.15 – Stud 1-5/8” x 13”	Bidder will like to propose the stud length per API 6A which is 12.750”. Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group B – Section D Item 4.5 – Blind flange	Kindly confirm the blind flange is with 9/16” autoclave box thread prep. or need to come with blind plug	Please provide as per SOR (with 9/16” autoclave box thread)
Group B – Section D Item 4.7 & 4.8 – Stud and Nuts	7/8” stud and nuts are for 2 1/16”-5,000 psi flange connection. For 2 1/16”-10,000 psi flange connection, bidder will provide 3/4” stud and nuts. Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group B – Section D Item 4.14 – 1-3/4” X 15.50”	Bidder will like to propose the stud length per API 6A which is 15.250”. Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group D – Section B Item 2.15 – Stud 1-5/8” x 13”	Bidder will like to propose the stud length per API 6A which is 12.750”. Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group D – Section C Item 3.7 & 3.8 – Stud and Nuts	7/8” stud and nuts are for 2 1/16”-5,000 psi flange connection. For 2 1/16”-10,000 psi flange connection, bidder will provide 3/4” stud and nuts. Kindly confirm acceptable.	Bidder to provide as per API 6A.

Group D – Section C Item 3.14 – 1-3/4" X 15.50"	Bidder will like to propose the stud length per API 6A which is 15.250". Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group E – Section B Item 2.15 – Stud 1- 5/8" x 13"	Bidder will like to propose the stud length per API 6A which is 12.750". Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group E – Section 3 Item 3.15 – Stud 1- 7/8" x 15"	Bidder will like to propose the stud length per API 6A which is 14.250". Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group F – Section A Item 1.14 – 1-3/8" X 11"	Bidder will like to propose the stud length per API 6A which is 10.750". Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group F – Section B Item 2.15 – 1-7/8" X 15"	Bidder will like to propose the stud length per API 6A which is 14.250". Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group G – Section A Item 1.11 – 1-7/8" X 15"	Bidder will like to propose the stud length per API 6A which is 14.250". Kindly confirm acceptable.	Bidder to provide as per API 6A.
Group B, D, E, F & G – Casing Head housing x slip on lock bottom	Kindly confirm either O-ring seal, Plastic energizer seal or FS- seal can be used for 24 1/2", 20", 13 3/8" or 9 5/8" casing.	Not acceptable, bidders are advised to quote as per SOR i.e. Slip on Lock bottom.
Diameter 4 1/2" face 5K pressure gauge	Bidder will like to offer diameter 4" face for 5K pressure gauge. Kindly confirm acceptable.	OK, acceptable.