

**CLARIFICATION # 1**

**TENDER # PROC-SERVICES/CB/P&P-5054/2021**

**HIRING OF SERVICES FOR EXECUTION OF ATA-2021 JOBS AT SINJHORO GAS FIELD**

Following clarifications have been made against subject mentioned tender:-

<b>Sr. #</b>	<b>Questions for Clarification</b>	<b>OGDCL Reply</b>
1	Please provide a tentative start date of TA.	The Tentative start date of ATA 2021 is 1 <sup>st</sup> September 2021.
2	Client to provide tentative area (m2) of painting so deployment can be estimated accordingly.	Area of insulation vide work order #129,130,131, 132 and 133 is 90 (m2); Estimated.
3	Client to provide a tentative area (m2) of Insulation so deployment can be estimated accordingly.	Area of painting vide work order# 134 and 135 is 90 (m2); Estimated.
4	In serial # 19 of Mechanical Section (Installation/Removal of scaffolding for NDT of piping and equipment).The Quantity of scaffolding is not mentioned. Please provide.	Scaffolding required for NDT jobs vide work order # 136 is 400 (m3); Estimated.
5	Class of Pipe, Drawing and Dia inch for each job is not mentioned for fabrication jobs in scope. Please provide.	<p>(i) Welding /Fabrication of Pandhi Tie-In project vide Work order #127 and 128, PEC design package is attached.</p> <p>(ii) Installation of isolation valve at instrument line A, vide work order #122. Drawing is attached.</p> <p>(iii) Installation of PSV isolation bypass vide work order# 123. Drawing is attached.</p> <p>(iii) Welding / Fabrication Jobs vide work order #125 and 126, may be cancel.</p> <p>Estimated total dia inch of welding/fabrication is 1100 dia inch of pipe welding. The schedule of pipe is 40/80/ 120 &amp; 160 and pipe sizes are multiple. Rate of welding / fabrication may be quoted per dia inch -schedule wise.</p> <p>However; for budget estimation for welding jobs, rate of schedule 80 may be referred for 1100 dia inch pipe welding.</p>