

	<b>MARU-RETI COMPRESSION PROJECT</b>		
	<b>Doc. Title:</b>	<b>General Clarification for Services of PC Contractor</b>	
	TENDER ENQUIRY NO.: <u>PROC-FC/CB/PROJ/MARU-RETI-5126/2021</u>		
	<b>Doc. No:</b>	<b>GC-001</b>	<b>Date: 18-10-21</b>

### **OGDCL Reply to PC Contractor Clarifications**

S. No.	PC Contractor Sought clarification	OGDCL Reply
1.	Please provide sub soil water level.	Site is mostly cultivated land exhibit high Sub soil water level (3-4ft)
2.	Regarding Dewatering, water disposal in existing drain channel. Please provide the distance between site & drain channel enable us to consider the temporary arrangements for disposal of water in channel.	As per the Volume-01, Section-II, Article 1.0, Sub-Article 1.6 of the Tender Document Contractor shall by site visit assess the requirements and obtain on their own responsibility all information that may be required and is necessary for preparing the Bid and entering into Contract with OGDCL.
3.	Is there any temporary road/access required to transportation/ handling of compressor skids, as the STERILE AREA, R: 40000 shown in foundation layout.	Sterile area is for permanent installation of equipment, nothing to do with transportation.
4.	Regarding the hookup of new compressor with existing compressor, please confirm that the cost of said job will be paid from BOQ described items.	There is no existing compressor while Hook up integration with existing system and pre- commissioning and commissioning already covered in prices summary table
5.	Reference to the item description of complete price summary mechanical work – A-1, “Fill of initial lube oil”. Please provide quantity of oil to be filled along with specification.	Initial fill for compressor will be provided by OEM.
6.	Reference to the item description of complete price summary mechanical work – A-1, Nitrogen Purging, please confirms that whole installed piping system of new compressor/ Hookup piping will be Nitrogen Purged.	Complete system will be Nitrogen urged by contractor
7.	Reference to the item description of complete price summary mechanical work – A-1, Leak test with process Gas, please confirm that process gas will be provided by client or will be arrange by contractor.	Client will provide the Process gas only, all other consumables/connections shall be the contractor’s responsibility.
8.	As the Appendix-A2, standard specification for insulation and Appendix-A6 wrapping and coating of underground piping are attached in bid documents but said items are not mentioned in BOQ. Please clear these activities will be required of not. If required. What will be the payment procedure	Piping specification is attached to define wrapping and coating requirement of piping. Contractor shall assess the same and cover this cost in Piping fabrication cost.

**MARU-RETI COMPRESSION PROJECT****Doc. Title:****General Clarification for Services of PC Contractor**TENDER ENQUIRY NO.: PROC-FC/CB/PROJ/MARU-RETI-5126/2021**Doc. No:****GC-001****Date: 18-10-21****Page 2 of 2**

9.	<p>Please provide vendor list for following items.</p> <ol style="list-style-type: none"><li>1- Bolt</li><li>2- Structural Steel (Locally) if required.</li><li>3- Paint material</li></ol>	<p>Bolt and Structural material shall be supplied in compliance with engineering drawings standard and specification. Contractor shall submit MTCs for all supply material.</p> <p>For Paint, Following vendors may be consider:</p> <p>Berger Kansai ICI Akzo Nobel Nippon</p>
----	---	---