



Dated: 28-07-2022

Clarification required for Procurement of Gas Detection System at OGDCL Dakhni Gas Field Tender Enquiry # PROC-FE/CB/PE&FD-5419/2022		
SR #	Descon Queries (28-07-2022)	OGDCL Response
1	All the cables shall be Flame Proof steel wired armored type.	Yes all the cables shall be Flame Proof steel wired armored type.
2	There is no requirement of Junction boxes and cables will be directly wired to Controller from detectors.	Yes Explosion Proof Junction boxes are required
3	As depicted in Section 3 of Tender document, Power supply for Controllers is 24 VDC. Please confirm either any battery backup is required to be considered or UPS Power is available at site.	UPS power supply is available at site
4	Considering distance of 100 Mtrs between Detectors and Controller. We understand that the cables will be directly buried in Trench. Please confirm.	Cables will be laid in cable trays (not in vendor scope)
5	No metallic Polyamide cable glands which are robust in design will be considered instead of metallic cable glands.	Vendor recommended Cable Glands
6	Please confirm OGDCL will provide boarding and lodging (food/accomodation) to vendor installation/commissioning team at site.	OGDCL will provide boarding and lodging (food/accomodation) to vendor's representative during installation/commissioning at site.