

CLARIFICATION NO. 04

PROC-SERVICES/CB/DO-6400000100/2022

HIRING OF DRILLING RIGS (2500-3000 HP) SERVICES

One of the Prospective bidders has made a query against the subject Tender Enquiry. The query along with OGDCL reply is given below for information of all the prospective bidders.

S.N.	TOR REFERENCE	COMPANY REQUIREMENT	CONTRACTOR CLARIFICATION	OGDCL RESPONSE
1.	RFQ, Service No. 1001960	Lump Sum rate for Mob Cost Beyond 20 Loads + 10%HC	Contractor's understanding is that this is related to transport of OGDCL loads above 20 loads during rig moves, which shall be reimbursable by OGDCL subject to the number of additional OGDCL loads. Kindly clarify that no rate is to be provided for this service as it will be on a case-by-case basis, with costs subject to the number of extra OGDCL loads.	Bidders Understanding is clear. The bidder is advised to quote the zero "0" rate for both Sub No 10.60 & 20.60 of RFQ, Service No. 1001960. In case bidder quotes the rate even after the clarification it will be considered as a zero rate. SCM deptt is requested that it will not be a part of the financial evaluation.
2.	Annexure A1, Section E (1 st bullet item)	BOPs e.g. Cameron, Shaffer, or Hydrill etc. or equivalent. BOP should be certified by OEM authorized / API approved workshop and certified to API Std 16AR RSL2 which is in accordance to API Std 53, 5th Edition, are acceptable . The workshop must be licensed to API 16A, API 6A and API Q1 and validity of certification should not be less than 05 years. The CONTRACTOR must have in place and carry out the manufacturer's recommended preventive maintenance program for all BOP equipment. Such program(s) are to be made available to COMPANY upon request. Each BOP stack shall be cleaned, visually inspected and serviced after every nipple down. All elastomers exposed to well fluids shall be changed at a minimum of every 30 months, unless visual inspection show the elastomers need to be replaced before this time.	With the current tender, in addition to standard OEM authorized certification for BOPs, OGDCL is also requesting additionally for RSL2 level certification as well. BOPs certified by OEM or OEM authorized workshops achieve the highest level of certification, similar to that at the time of manufacturing. Additional inspection/certification, such as to RSL2 level is generally only requested when 3 rd party workshops are not an OEM authorized facility. Accordingly, we kindly request clarification that RSL2 level certification is not required for BOP certified by OEM or OEM authorized workshops, as per general industry standards. Kindly note, BOPs certified at OEM authorized or non-OEM authorized workshops shall in any case be in accordance to API STD 53, 5th addition and shall be licensed to API 16A, API 6A and API Q1 .	RSL2 level certification is not required for BOP's serviced from the OEM authorized workshop. RSL2 level certification is only required for BOP's serviced from those workshops which are not OEM authorized. Rest remain the same as per TOR.
3.	Annexure A2, Services	Accommodation and catering on the Drilling Rig for extra COMPANY's Personnel or COMPANY's 3rd party personnel as per requirement (+30 persons) – Category 3	Kindly clarify that catering and accommodation for extra COMPANY's Personnel or COMPANY's 3rd party personnel above 20 persons shall be at Category 3, in accordance with other sections of the tender documents.	As per Annexure A2, Services: The bidder must have enough capacity to handle more than 30 company personnel and provide accommodation and catering. However, the catering rates shall be applied to the attendance exceeding 20 personnel as per TOR as per Annexure A5-1 clause h catering rates.