

Clarification No 4 & 5

Tender Enquiry No: Tender PROC-FB/CB/DRLG/D-5091/21
Description: PROCUREMENT OF REAMER SHOE AND TORQUE RINGS

Clarification 4 :

- What kind of torque requirement is needed or What kind of torque is expected to see on the connections?
- If you are installing the ring in the float equipment, can we get a drawing of the float equipment and the connection?

Reply:

1. 100% connection torque. Casing reaming torque which is normally 100% connection make up torque
2. Torque rings will only be installed over BTC connections. Torque limit should be higher than connection torque due to torque rings installation so the casing reaming can be performed

Clarification 5:

1. Reamer shoe, please confirm the OD (open hole diameter).
2. For 14", it is not API size, there is no BTC thread .

Reply: type of Rib OD is required for the reamer shoes is as under
22"hole section recommended 20"-21"
17-1/2"hole section recommended 15-1/2"-15-3/4"
12-1/4"hole section recommended 11-3/4"-11-1/2"

2.Please provide BTC threads as per SOR, in case of dimensions/thread profile required please contact casing pipe/thread