

## **Clarification No. 01**

### **TENDER ENQUIRY NO. PROC-SERVICES/CB/P&P-5083/2021** **Hiring of services for installation of Filter Coalescer Vessel** **(FC-101) including fabrication, welding, cutting, installation,** **painting etc. of associated piping along with relevant E&I** **jobs at Qadirpur plant**

Some of the Prospective bidders have made a few queries against the subject Tender Enquiry. The queries along with OGDCL replies are given below for information of all the prospective bidders.

<b>S.No</b>	<b>Clarification/Query</b>	<b>OGDCL REPLY</b>
1	Point # 4 of Contractor's responsibility deduces that there will be no E&I job in contractor scope of work. Only mechanical connections will be provided for instruments installation. Please confirm	Follow Clause 4 of the section INSTALLATION OF FILTER COALESCER under CONTRACTOR'S RESPONSIBILITIES in TOR's
2	Is there any painting/insulation of the vessel? Please confirm. If yes, please provide specification of the insulation of both vessel and piping.	No
3	Point # 5 of inspection and testing states RT % as 30% while in drawings RT requirement is 10%. Please clarify.	RT is 30% (Follow Clause 5 of the section INSPECTION & TESTING under CONTRACTOR'S RESPONSIBILITIES in TOR's)
4	There is no requirement of welders qualification test mentioned in ITB. Please advise if it is required.	Contractor's approved welders are acceptable. Client will not conduct test. Welder qualification test record by Contractor to be provided.
5	Priced BOQ requires cost break up for sand blasting and painting while there is no painting required for piping as per Isometric drawings. Please clarify.	Painting/sandblasting of piping is required.
6	Please advise dates for the execution of the project and Material (Piping, insulation, structure and supports material) availability for execution.	In 3rd Week of September, 2021 Tentatively