

**CLARIFICATION NO.1**  
**PROC/LF/PT/D(RMP)-18520/21**  
**MUD TANKS**

---

- Only butterfly Valves and other solid control equipment (shale shakers, mud cleaners, degasser, centrifuge, pumps, gun lines) will be supplied by OGDCL and fabrication / provision of foundations for placing/fitting these assys is the responsibility of contractor.
- Fabrication / provision of vertical suction valves / bridge valves shall be responsibility of contractor.
- Provision / fabrication of all the connections/piping/flow lines/flanges for valves, partition , pedestal for agitators, stairs, grating, walkways etc as existed in tanks is the responsibility of contractor.
- Couplings for interconnection of tanks should be Kemer hammer union seal type as per terms and conditions.