

Pre-Bid Clarification No. 2

Tender Enquiry PROC-FE/CB/PE&FD-5274/2022

Wellhead Control Panels

Sr.No	Bidder's Question	OGDCL's Reply
1	Can you please advise on the gas composition (% of H ₂ S) as this is sour gas driven unit? Currently, we have considered standard NACE compliant valves and materials as gas composition is not available in the specification	The range of following two components in Gas Composition of various Fields is as under:- H ₂ S (0 to 150 PPM) CO ₂ (0.3 to 6 Mol%)
2	The Exhaust from the pump and the logic valves (gas operated) – We propose to vent this through a common gas vent (tubed to a bulkhead on the panel).	Output from POV1 Valve & Output from POV2 can be combined together for return of hydraulic Oil to Reservoir Tank, however that common line will have pressure rating equal to SSSV line. In addition to this, manufacturer will provide warranties/Guaranties of its smooth operation as per Tender Requirement.
3	The skid mounted WHCP shall be made of stainless steel and painted to finished coat. Panel shall be suitable for zone 2 hazardous area installation with: i. Frame work ii. Roof With Sun Shade iii. Bottom Plate and Plinth iv. Front & Back Door	The skid mounted WHCP shall be made only of stainless steel and paint is not required.