

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION B

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material 3-1/2 INCH SEAMLESS PRODUCTION TUBING, 12.7 PPF, SUPER 13 CHROME, 95 KSI, CAL-IV TESTED WITH PUP JOINTS & X-OVERS
Tender Enquiry No PROC-FB/CB/PE&FD-5259/2022
Due Date
Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	Seamless Production Tubing 3-1/2" 12.7 ppf Super 13 Chrome Material, 95 Ksi CAL IV Tested Premium Thread Connections (Threaded and Coupled) ISO 13680/API 5CRA, Group-1 Martensitic Steel (13-5-2) PSL-1, R2. Details are in attached Sheets	Meter	15000					
2	Pup Joint with same quoted tubing thread connections Box X Pin Length = 2 Feet Material Super 13 chrome 95 Ksi	Number	8					
3	Pup Joint with same quoted tubing thread connections Box X Pin Length = 3 Feet Material Super 13 chrome 95 Ksi	Number	8					
4	Pup Joint with same quoted tubing thread connections Box X Pin Length = 5 Feet Material Super 13 chrome 95 Ksi	Number	8					
5	Pup Joint with same quoted tubing thread connections Box X Pin Length = 7 Feet Material Super 13 chrome 95 Ksi	Number	8					
6	Pup Joint with same quoted tubing thread connections Box X Pin Length = 10 Feet Material Super 13 chrome 95 Ksi	Number	8					
7	X-Over Box 3-1/2" 13.3 ppf IF Threads X Pin 3-1/2" 12.7 ppf with same quoted tubing threads connections Length = Min 2 Feet, Material Min L-80 or Equivalent Grade	Number	4					
8	X-Over Pin 3-1/2" 12.7 ppf with same quoted tubing thread connections X Pin 3-1/2" 12.7 ppf Vam Top Threads Length = Min 2 Feet, Material Super 13 Chrome 95 Ksi	Number	4					
9	X-Over Box 3-1/2" 12.7 ppf with same quoted tubing thread connections X Pin 3-1/2" 12.7 ppf Vam Top Threads Length = Min 2 Feet, Material Super 13 Chrome 95 Ksi	Number	8					
10	X-Over Box 3-1/2" 12.7 ppf Vam Top Threads X Pin 3-1/2" 12.7 ppf with same tubing thread connections Length = Min 2 Feet, Material Super 13 Chrome 95 Ksi	Number	6					
11	X-Over Box 3-1/2" 12.95 ppf Hydril PH-6 or Equivalent premium threads X Pin 3-1/2" 12.7 ppf Vam Top thread connections Length = Min 2 Feet, Material Super 13 Chrome 95 Ksi	Number	8					
12	X-Over Box 3-1/2" 12.7 ppf Vam Top threads X Pin 3-1/2" 12.95 ppf Hydril PH-6 or Equivalent premium thread connections Length = Min 2 Feet, Material Super 13 Chrome 95 Ksi	Number	6					
13	X-Over Pin 3-1/2" 12.7 ppf Vam Top threads X Pin 3-1/2" 12.95 ppf Hydril PH-6 or Equivalent premium thread connections Length = Min 2 Feet, Material Super 13 Chrome 95 Ksi	Number	4					

Note: 1) BID VALIDITY: BID MUST BE VALID FOR 120 DAYS FROM BID OPENING DATE.
2) BID BOND AMOUNT: US\$62,000/- OR EQUIVALENT PKR TO BE SUBMITTED WITH TECHNICAL BID AND VALID FOR 210 DAYS.
(3) DELIVERY PERIOD: EIGHT (08) MONTHS FROM L/C ESTABLISHMENT DATE.
(4) EVALUATION CRITERIA: "FULL CONSIGNMENT WISE" ON CFR BY SEA KARACHI-PAKISTAN BASIS.
(5) TENDER DOCUMENTS AVAILABLE ON OGDCL'S WEBSITE UNDER TAB "MASTER SET OF FOREIGN TENDER DOCUMENT (PRESS-SINGLE STAGE TWO ENVELOP) 05-01-2022

Seamless Production Tubing 3-1/2" 12.7 PPF, Super 13 Chrome Material, Min 95 KSI Yield Strength CAL – IV Tested Premium Threads Connection (Threaded & Coupled) along with Pup Joints and X-overs in compliance with ISO 13680/API 5CRA, Group 1 Martensitic Steel (13-5-2) PSL-1, R2 latest edition of ISO 11960/API 5CT in accordance with NACE MR-0175/ISO15156

Sr #	Description	Quantity	Unit CFR (USD)	Total CFR (USD)
1.	<p>Seam Less Production Tubing 3-1/2", 12.7 PPF, with Cal IV tested Premium Thread Connections (BXP) Threaded and Coupled Super 13 Chrome material 95 Ksi Drift Dia 2.625" having the following chemical and mechanical properties</p> <p><u>Chemical Composition</u> As per ISO 13680/API 5CRA for Group-1 Martensitic Steel (13-5-2) Super 13 chrome Material Min 95 Ksi Yield Strength</p> <p><u>Physical Properties</u> As per ISO 13680/API 5CRA for Group-1 Martensitic Steel (13-5-2) Super 13 chrome Material Min 95 Ksi Yield Strength</p> <p>Bidders are strictly advised to submit chemical composition and Physical Properties of their quoted tubing along with their Technical and Financial Bid</p>	15,000 Meters		
2.	<p>Pup Joint with same quoted tubing thread connections Box X Pin Length : 2 feet Material : Super 13 Chrome 95 Ksi</p>	8 Nos		
3.	<p>Pup Joint with same quoted tubing thread connections Box X Pin Length : 3 feet Material : Super 13 Chrome 95 Ksi</p>	8 Nos		
4.	<p>Pup Joint with same quoted tubing thread connections Box X Pin Length : 5 feet Material : Super 13 Chrome 95 Ksi</p>	8 Nos		
5.	<p>Pup Joint with same quoted tubing thread connections Box X Pin Length : 7 feet Material : Super 13 Chrome 95 Ksi</p>	8 Nos		
6.	<p>Pup Joint with same quoted tubing thread connections Box X Pin Length : 10 feet Material : Super 13 Chrome 95 Ksi</p>	8 Nos		

7.	X-Over, BOX 3-1/2" 13.3 PPF, IF threads X PIN 3-1/2", 12.7 PPF, with same quoted tubing threads connections Length: Min 2 feet. Material : Min L-80 or Equivalent Grade	4 Nos		
8.	X-Over, PIN 3-1/2", 12.7 PPF, with same quoted tubing thread connections X PIN 3-1/2", 12.7 PPF Vam Top threads Length: Min 2 feet. Material : Super 13 Chrome 95 Ksi	4 Nos		
9.	X-Over, BOX 3-1/2" 12.7 PPF, with same quoted tubing threads X PIN 3-1/2" 12.7 PPF Vam Top Threads Length : Min 2 feet Material : Super 13 Chrome 95 Ksi	8 Nos		
10.	X-Over, BOX 3-1/2" 12.7 PPF, Vam Top threads X PIN 3-1/2" 12.7 PPF, with same quoted tubing thread connections Length : Min 2 feet Material : Super 13 Chrome 95 Ksi	6 Nos		
11.	X-Over, BOX 3-1/2" 12.95 PPF, Hydril PH-6 or equivalent premium threads X PIN 3-1/2" 12.7 PPF, Vam Top thread connections Length : Min 2 feet Material : Super 13 Chrome 95 Ksi	8 Nos		
12.	X-Over, BOX 3-1/2" 12.7 PPF Vam Top threads X PIN 3-1/2" 12.95 PPF Hydril PH-6 or Equivalent premium threads Length: Min 2 feet. Material : Super 13 Chrome 95 Ksi	6 Nos		
13.	X-Over, PIN 3-1/2" 12.7 PPF Vam Top threads X PIN 3-1/2" 12.95 PPF Hydril PH-6 or Equivalent premium threads Length: Min 2 feet. Material : Super 13 Chrome 95 Ksi	4 Nos		

Total Quoted Cost

XXXXXXXXXX

[Handwritten signature]

<u>Terms and Conditions:</u> <u>Every bidder must comply the following conditions in order to be considered for Technical Evaluation. All the required supporting documents must be submitted where applicable. Bidders failing to fulfil any of the requirement mentioned below would not be considered for further Evaluation and Technically Disqualified without seeking any Clarifications.</u>		Bidder to comply /confirm the following in the Table and provide necessary documents accordingly.
1	<u>Technical and Financial Bids</u>	
1.1	Bidder are required to submit Technical & Financial bids in two envelopes separately	
2	<u>Authority Letters</u>	
2.1	In case the bidder and pipe manufacturer are different, than the bidder must provide an original authority letter/OEM certificate from the pipe manufacturer. The authority letter must be on company letter head, showing the name and contact details official E-mail of the signing authority.	
2.2	In case the pipe manufacturer and threader are different, than the bidder must provide an original authority letter/OEM certificate from the pipe manufacturer in favor of threader. The authority letter must be on company letter head, showing the name and contact details official E-mail of the signing authority.	
2.3	The bidder will also provide a similar letter in case they have their local agent in Pakistan. The authority letter must be on company letter head, showing the name and contact details official E-mail of the signing authority	
2.4	Bidders are required to clearly mention the name of Manufacturer and threader of Tubing, Pup Joints and X-overs separately against each line item	
3	<u>Manufacturing Plant (s) API Certificates</u>	
3.1	<u>API 5CRA</u> Bidders are required to submit API-5CRA licenses of its quoted manufacturing plant (s) for this specific tender must be active at the time of bid submission. The license must mentioning to manufacture Corrosion Resistant Alloy Seamless Tubes for use as Tubing and Coupling Stock Group-1, Category 13-5-2, Grade 95 Ksi. The bidder to provide copies of the manufacturer API 5CRA certificates as a proof	
3.2	<u>API 5CT</u> Bidders are required to submit API-5CT licenses of its quoted manufacturing plant (s) for this specific tender must be active at the time of bid submission certified by API under Specs. 5CT & Q1 for the last ten (10) years, for the date of tender opening. The bidder to provide copies of the relevant API certificates as a proof.	
3.3	<u>Threader Experience of Cal IV Tested Premium Threads Tubing</u> In case the threader(s) is (are) different from the tubing manufacturer then the threader(s) must have a minimum of 10 year experience in cutting the CAL IV	

	tested premium threads from the date of tender opening. Documentary evidence must provide with the technical bid	
4	<u>Financial Statements</u>	
4.1	In case bidder has not supplied super 13 chrome material tubular to OGDCL then it is required to submit original print of the annual audited accounts reports for the last 03 consecutive years (along-with attested English Copies) in order to verify its liquidity position, revenues, profitability of the company.	
4.2	In case manufacturer has not supplied super 13 chrome material tubular to OGDCL then it is required to submit original print of the annual audited accounts reports for the last 03 consecutive years (along-with attested English Copies) in order to verify its liquidity position, revenues, profitability of the company.	
4.3	In case of weak financial statement the bid will not be acceptable	
5	In case bidder has not supplied super 13 chrome material tubulars to OGDCL then it is required to confirm production of its quoted manufacturing plant(s) for super 13 chrome material seamless tubing which must not be less than 2000 Metric tons of tubing per year. Bidder will provide the certificate in this regard from the manufacturing plant	
6	<u>Supply record and performance certifications of the Super 13 chrome CAL IV Tested premium threads tubing (Threaded and coupled)</u>	
6.1	Manufacturer must have manufactured & supplied CAL IV tested premium threads production tubing (threaded and coupled) Super 13 Chrome or higher to the multinational E&P companies like ExxonMobil, PDO, KOC, Shell, BP, Total, ENI, OMV, MOL and other renowned E & P companies (not belonging to the manufacturer's country) in excess of 1,000,000 meters during the last 10 years. Moreover the supply to the following E & P companies operating in Pakistan will also be considered like PPL, Mari, POL, UEPL, etc. The supply record must confirm this fact. The supply record must be independently verifiable i.e. the latest contact details (name, designation, official e-mail etc.) of the relevant persons in all the major customer organizations must be mentioned	
6.2	In case the bidder is not the pipe manufacturer than the bidder has also to provide its own supply record of super 13 chrome material tubing from the quoted manufacturer (s) in order to ascertain its experience in this field.	
6.3	Bidder must also provide the supply record of the threader(s), in case it is (are) different from the tubing manufacturer(s). The threader must have cut and supplied at least 1,000,000 end Joints chrome grades CAL IV tested premium threads tubing to different multinational E&P companies or other renowned E & P companies (not belonging to the manufacturer's country) in the last 10 Years	
6.4	Supply record comprising the super 13 chrome tubing sold to supply houses will not be considered.	
6.5	If the bidder/Manufacturer has not already supplied threaded and coupled premium threads tubing with super 13 chrome grade to OGDCL then certificates of satisfactory performance in favor of bidder/pipe manufacturer(s)/threader(s) issued by authorized officials of at least 03 different multinational E&P companies like Exxon, PDO, KOC, Shell, BP, Total, ENI, OMV, MOL or other renowned E & P companies (not belonging to the manufacturer's country) or Pakistan based E & P companies like PPL, Mari, POL, UEPL regarding the quoted threads must be provided with the bid. The certificates must on the company letterhead hard copy	

	<p>or official email should indicate the Name and Designation of the signing authority along with his complete contact details in order to verify the same are acceptable It is suggested that the certificates should preferably of a pattern providing the following information:</p> <ul style="list-style-type: none"> i. Delivery period compliance ii. Performance of supplied super 13 chrome tubing iii. Performance of supplied CAL IV tested premium threads of tubing 	
6.6	Certificates/Emails issued by supply houses etc. will not be considered	
6.7	Bidders or Manufacturers who have provided the chrome or higher material tubing, pup joints and X-overs to OGDCL in the past and already fulfill the pre requisite criteria are required to submit the copies of purchase orders issued to them by OGDCL against the requirement at 6.1 to 6.6	
7	<u>Delivery Requirements</u>	
7.1	The desired delivery period is 08 months C&F by Sea Karachi from the date of LC establishment.	
8	<u>Quoted Tubing and Pup Joints CAL IV tested Premium Threads Connections</u>	
8.1	The manufacturer/threader must have capability to provide thread connections which are tested in compliance with ISO-13679 2002 or API 5C5 2017 Application Level CAL-IV test. Test report for the quoted premium thread tubing covers the range of the quoted thread/weight/size report showing the compatibility of the testing/qualification records with extrapolation/interpolations rules of ISO-13679 2002 ANNEX G or API 5C5 2017 must be submitted. ('Petroleum and natural gas industries —Procedures for testing casing and tubing connections').	
8.2	The Tensile, Burst & Collapse rating of the Quoted Premium Thread Connections must be equal to or exceed those of the Pipe body ratings whereas the compression rating of the quoted threads should not be less than 80% of the pipe body compression rating. Documents supporting the requirement should be provided along with the technical bid	
9	<u>General Requirements</u>	
9.1	Running / Pulling, handling procedures& required torque values for the quoted tubing is to be submitted along with the technical quotation	
9.2	The bidder to confirm tubing tally specifying the length of individual joint is to be provided along with the shipping documents	
9.3	The bidder to confirm clearly in the Bid documents that the material test certificates will be provided with the shipping documents.	
9.4	Bidder must provide the detailed technical literature/documents for the manufacturing/threading company.	
9.5	All X-Overs and Pup Joints should also be of Super 13 Chrome Material 95 Ksi as specified for Seam less Production Tubing at Serial No 1. Except for X-Over at Serial No 7 which is to be of Min L-80 or equivalent grade material Requirement.	
9.6	Bidder is required to submit the technical data sheets of the quoted tubing confirming the Tubing size and weight in ppf, Chemical composition, Material grade, Thread name, Pipe properties, Connection properties, Connection performances, ODs, IDs, Drift ID, Range, Burst and Collapse pressures etc.	

10.	<p><u>THIRD PARTY INSPECTION (TPI)</u></p> <ol style="list-style-type: none"> 1. OGDCL will arrange the Third Party Inspection, Bidder is required to confirm that they will provide necessary assistance to Third Party Inspection (TPI) company. Third Party Inspection reports verified by OGDCL will be provided with the shipping documents for LC encashment, Bidder is required to confirm that they will timely inform the relevant TPI company and provide the necessary assistance during the inspection. 2. Inspection may require at least 5 to 6 or more visits to the manufacturing plants and may involve 8 to 10 Man days or more. Bidder is required to confirm that they will timely inform the relevant TPI company and provide the necessary assistance during the inspection <p><u>Tentative Scope of Third Party Inspection</u></p> <ol style="list-style-type: none"> 3. Third Party Inspector to confirm that the Tubing is brand new/unused 4. Visual and dimensional inspection of body on-spot basis covering at least 10% of the complete lot. 5. Visual and dimensional inspection of Thread on-spot basis covering at least 10% of the complete lot. 6. Review of Mill Test Certificates. 7. Review of Hydro-test Reports 8. Marking verifications of the Tubing Joints. 9. Preparation of Inspection report in light of the Certificates and Tally sheets. 10. Vetting of Marking, Packing/Bundling and quantity as per Contract. 11. Third party inspection company will submit inspection progress reports to OGDCL PE & FD at following e-mails addresses: 12. pir_asim@ogdcl.com, hameed_afzal@ogdcl.com, kafeel.ahmed@ogdcl.com, adeel_saleemi@ogdcl.com, omer_ali@ogdcl.com <p><u>Submission of Final Inspection report</u></p> <ol style="list-style-type: none"> 13. Place the signature /stamp on inspection release note/inspection report electronically in the original pdf files of inspection release note and inspection report. 14. Mention OGDCL purchase order number and LC number in the first page of final inspection report/inspection release Note. 	
11	<u>General Specifications of the Production Tubing. Bidder is required to confirm</u>	
11.1	Tubing joints should be provided in range R-2	
11.2	Tubing, pup joints & X-overs should be of seamless steel	
11.3	The length of each X-over should not be less than 2 feet.	
11.4	Tubing, pup joints & X-overs ends should be provided with proper thread protectors and exposed threads must be protected with an anti-corrosion storage compound as per API recommendations for Super 13 Chrome material.	
11.5	Delivery Tolerance = +0% – 3% of item no-1 Tubing in Quantity and Value is allowed however the payment will be made as per the actual quantity of tubing delivered/received.	

<u>Other Terms and Conditions</u>		
1	Clean Acceptance of terms & conditions of Tender Document, Schedule of Requirement is required from the Bidder.	
2	Shipment from ACU Member Countries: In case of Shipment from ACU Member Countries, the LC beneficiary should be of that particular country from where the consignment is being shipped	
3	<p>Foreign Procurement Payment Terms (Competitive Bidding, Pre-qualification and Proprietary Mode of Procurement): Following payments methods have been approved for Competitive Bidding/Press Tender, Prequalification and Proprietary mode of procurement effective from February 27, 2018.</p> <p><u>i. Tender value less than or equal to US\$ 200,000:</u></p> <p>Payment to the Contractor/ bidder in foreign currency shall be made by establishing in favor of the Contractor an irrevocable Letter of Credit (hereinafter called the L/C). 70 % Payment (s) under the L/C will be made for the FOB/ CFR / CPT (as the case may be) price of material of each shipment upon submission of the shipping documents. Balance 30% Payment will be released after receipt, inspection and acceptance of material.</p> <p><u>ii. Tender value more than US\$ 200,000:</u></p> <p>Payment to the Contractor/ bidder in foreign currency shall be made by establishing in favor of the Contractor an irrevocable Letter of Credit (hereinafter called the L/C). 80 % Payment (s) under the LC will be made for the FOB/ CFR / CPT (as the case may be) price of material of each shipment upon submission of the shipping documents. Balance 20% Payment will be released after receipt, inspection (in addition of pre-shipment inspection) and acceptance of material.</p>	
4	<p>The Bidding Procedure is "Single Stage - Two Envelope Procedure":</p> <p>All bidders are required to carefully read bidding procedure and terms & conditions elaborated in OGDCL's Tender Document uploaded on Company's website under heading "MASTER SET OF FOREIGN TENDER DOCUMENT (PRESS-SINGLE STAGE TWO ENVELOP) 05-01-2022</p>	