

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION E

(To be completed, filled in, signed
and stamped by the principal)

ANNEXURE 'A'

Material BUG BLOWERS FOR PRODUCTION FIELDS
Tender Enquiry No PROC-FE/CB/PROD-3068/2017
Due Date
Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

| Sr No | Description | Unit | Quantity | Unit Price (FOB) | Total Price (FOB) | Unit Price C & F BY SEA | Total Price C & F BY SEA | Deviated From Tender Spec. If Any |
|-------|---|--------|----------|---------------------|----------------------|----------------------------|-----------------------------|--------------------------------------|
| 1 | BLOWER BUG 50", SUPPLY 230 V, HEAVY DUTY STEEL FRAME, IMPELLER 48" (CAST AL), 5 HP EX-PROOF MOTOR WITH IEC EXPROOF STARTER, 1200 RPM, CORROSION RESISTANT, 100 METER WEATHER PROOF COPPER PVC CABLE (SIZE AWG = 10, 4 CORE, 600 VAC, 90 DEG. C. | Number | 25 | | | | | |

Note: (1) PURSUANT TO TENDER CLAUSE # 2.2, 11.4, 13 & 35.3.2. BID BOND AMOUNTING TO US\$ 3000/- (US DOLLAR THREE THOUSAND ONLY) SHOULD BE SUBMITTED WITH THE TECHNICAL BID
(2) EVALUATION CRITERIA : FULL CONSIGNMENT WISE ON C&F BY SEA, KARACHI (3) TECHNICAL SPECIFICATION PAGE ATTACHED

BUG BLOWER

Specifications

- Bug Blower size 50"
- Supply voltage 230 VAC, 3-Phase
- Heavy Duty Steel Frame
- Impeller size 48" (CAST ALUMINUM)
- 5 HP Explosion Proof Motor with IEC Explosion Proof Starter, 1200 RPM
- Corrosion Resistant
- Weather Proof Armored Copper PVC Cable, 80 Meter (Size AWG=10, 4 Core, 600 VAC, 90 Deg. C), Plain Annealed Stranded Copper for the conductors/ cores, cross-linked polyethylene (XLPE) for the insulation, Steel Wire for the Armored and PVC (Polyvinyl Chloride) for the bedding and sheathing.