

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION A

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Page 01/02

Material MEG INJECTION PUMP WITH EXPLOSION PROOF MOTOR
Tender Enquiry No PROC-FA/CB/P&P/PUMP-4411/2019
Due Date 18-07-2019
Evaluation Criteria MAIN ITEM

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	Complete MEG Pump along with Explosion Proof Motor, as per attached specification & TOR	Number	1					
2	02 years operational spare parts of MEG Pump	Number	1					

- Note:
1. **Bid bond and Bid Validity:**-Pursuant to tender clause # 2.2, 11.4, 13 & 35.3.2, bid(s) must be accompanied by an upfront bid bond in the form of pay order/ demand draft or bank guarantee issued by scheduled bank of Pakistan or a branch of foreign bank operating in Pakistan, for an amount of **US\$ 600/-** (US\$ Six hundred only) or equivalent Pak Rupees, with technical bid and valid for 150 days from the date of opening of the bids. The bank guarantee must be issued in accordance with the format as per Annexure-C of the tender documents.
 2. **Shipment from ACU member Countries:** In case of shipment from ACU member countries, the LC beneficiary should be of that particular country from where the consignment is being shipped.
 3. **Terms and conditions:**-Bidders are advised to carefully read all the terms and conditions of the Tender Document available at OGDCL web site in the master tender document.
 4. **Summary rejection criteria:** - The summary rejection criteria at clause 35 of the tender document may also be examined carefully. Any bid not meeting the criteria spelled in the clause # 35 shall be summarily rejected without any right of appeal. The detailed tender document is available on OGDCL website as "Master set of tender document-Foreign".
 - 5 **Payment Terms:** Clause No: 3 of Section-III (Part-B) i.e. Conditions of Contract "Special" of Tender Document has been amended and following will be the payments methods.
 - i. **Tender value less than or equal to US\$ 200,000:**-Payment to the Contractor/ bidder in foreign currency shall be made by establishing in favor of the Contractor an irrevocable Letter of Credit (hereinafter called the L/C). 70 % Payment (s) under the L/C will be made for the FOB/ CFR / CPT (as the case may be) price of material of each shipment upon submission of the shipping documents. Balance 30% Payment will be released after receipt, inspection and acceptance of material.
 - ii. **Tender value more than US\$ 200,000:** Payment to the Contractor/ bidder in foreign currency shall be made by establishing in favor of the Contractor an irrevocable Letter of Credit (hereinafter called the L/C). 80 % Payment (s) under the L/C will be made for the FOB/ CFR / CPT (as the case may be) price of material of each shipment upon submission of the shipping documents. Balance 20% Payment will be released after receipt, inspection (in addition of pre-shipment inspection) and acceptance of material.

02/02

**SPECIFICATION AND TERMS AND CONDITIONS FOR SUPPLY OF
MEG PUMP AT CHANDA PLANT:**

1. SPECIFICATIONS OF MEG INJECTION PUMP:

- Tag # P-200 (For OGDCL Ref. only)
 - Flow rate 1.4 GPM (minimum), Volumetric Efficiency: 93% (minimum)
 - Stroke: 60-130 per minute, Test pressure (Hydrostatic): 1276 PSIG (minimum)
 - Set pressure of internal Relief Valve: 1000 PSIG (minimum)
 - NPSH Required: 3m WC
 - Discharge pressure: 850 PSIG (minimum), Suction pressure: 0 PSIG
 - Set pressure for Safety Valve: 935 PSIG
 - Fluid: Mono Ethylene Glycol (MEG), Fluid Temp Min/Max: 80/200 F,
 - Fluid Density: 1.15 g/cm³, Fluid Type: Clean
 - Fluid Vapor Pressure: 0 bara
 - Explosion Proof Motor
2. Manufacturer of Pumps should have 5 years of manufacturing experience.
 3. Technical brochure of MEG pump to be provided with Technical bid.
 4. Operational & Maintenance manual must be provided with the supply of pump.
 5. Delivery period for material is 120 days from the date of issuance of L/C.
 6. Bidder must ~~be~~ provide documentary evidences for the supply of pumps, besides unpriced copy of contract, purchase order with name and full contact details to be provided in technical bid.
 7. List of 02 years' spare parts to be attached with bid (with cost of each spare part). The cost of 02 years' spare parts will not be included in financial evaluation. OGDCL will select the spare parts at its own choice.
 8. Guarantee / warrantee for the equipment for a period of 01 years after being taken into service or 18 months after shipment, whichever completes earlier.