



UCH COMPRESSION PROJECT



Design Engineering, Procurement (Supply), Construction, Installation/Erection, Pre-Commissioning, Commissioning & Start-up (including performance testing and Reliability Guarantee Test) of Compression System at UCH Compression Project
Tender Enquiry No. PROC-FC/CB/PROJ/UCH(COM)-4462/2019

PRE-BID CLARIFICATION # 30

Item No.	Tender Document Reference	Query	Response
1	4985-ILT-6302-5 Control Room Plan <u>New heat losses inside Control Room</u>	According to available spaces in Control Room for required new Server cabinets / I/O cabinets / DCS cabinets / F&G cabinets / Ows / printers installation, Bidder understand existing HVAC system is already sized to remove new installations heat losses. Company is kindly request to confirm Bidder understanding.	Numerous Split type ACs are already installed to cater the Control room existing requirement, and we understand that these will be also sufficient to cater new additional panel/cabinets heat losses. However, it is bidder's responsibility to provide AC/heat calculation of overall control room considering new panel heat losses and advise for any additional split type AC requirement, so that same shall be installed/added by OGDCL maintenance team itself in future.